



Construction Considerations for a CHP Facility Conversion in a Clustered Urban Setting

BOLDT®

BEYOND
125
YEARS

Charter Street Heating Plant
University of Wisconsin – Madison, WI

Project Timeline and Picture

Sierra Club Files Lawsuit

(Court finds 3 projects violated the Clean Air Act NSR provisions)

2007

Broke Ground

October 25th

2010

Substantial Completion

November

2013

- Street Plant is one of two power plants run by the university

- Plants serve 43,000 students and 330 buildings

- A true tri-generation plant

- Plant can never afford to go offline for extended period due to service needs

- Charter Street Plant is an urban, brownfield site, surrounded by a bustling urban area:

- Student housing, urban development, sporting venues, bike path, roads, and a rail line

Our Mission:

Convert plant from coal to gas without disrupting service to the university.

Scope of Work

\$140M Joint Venture with AMEC converting plant from coal to gas.

Demolition scope included:

- Four underground fuel oil tank's
- Four coal boilers
- Coal handling equipment (yard and internal transfer)
- Two baghouses, stack and ash handling equipment


Installation of the following major components:

- Four ultra low NOx natural gas/fuel oil package boilers
- 71,000 SF for new boiler, control room and water treatment
- Plant of Plant including a 920,000 gal fuel oil storage tank
- Digital controls for both campus heating/cooling plants
- Electrical system upgrades and additions(13.8-KV switchyard)
- Fire protection for the existing plant and expansion



*All work completed while the plant remained on line.
A prolonged outage was out of the question.*

Setting




“Before” Aerial Image




Work – Pre-Construction Phase



Work – Pre-Construction Phase



Work – Pre-Construction Phase



Work – Pre-Construction Phase



Work – Phase 1



Work – Phase 1 Gas Boiler Building and Fuel Oil Tank




Work – Phase 2




Demo of Coal
Handling
Equipment, Ash
Silo, Baghouse
and Chimney

Work – Phase 2 – Coal Yard & Baghouse Demo




Work – Phase 3



Work – Phase 3




Work – Phase 4



Work – Phase 4



Work – Phase 5



Work – Phase 5 - Cooling Tower/Water Treatment Building Installed



Work – Phase 6



Typical Construction Considerations and Mitigation

- Safety
- Soils
- Groundwater
- Surface water management
- Dust
- Noise
- Weather-Related Planning
- Limited lay-down space required "just-in-time" deliveries to keep the project on schedule



Unique Construction Considerations and Mitigation

- **Utilities (gas, electric, cable lines, sewer, water)**
- Fuel oil back-up
- Tall Structures Demo
- Traffic
- Campus event planning
- Crane size optimized for scope of work and logistics
- Extensive planning for crane picks



Unique Construction Considerations and Mitigation

- Utilities (gas, electric, cable lines, sewer, water)
- **Fuel oil back-up**
- Tall Structures Demo
- Traffic
- Campus event planning
- Crane size optimized for scope of work and logistics
- Extensive planning for crane picks



Unique Construction Considerations and Mitigation

- Utilities (gas, electric, cable lines, sewer, water)
- Fuel oil back-up
- **Tall Structures Demo**
- Traffic
- Campus event planning
- Crane size optimized for scope of work and logistics
- Extensive planning for crane picks



Unique Construction Considerations and Mitigation

- Utilities (gas, electric, cable lines, sewer, water)
- Fuel oil back-up
- **Tall Structures Demo**
- Traffic
- Campus event planning
- Crane size optimized for scope of work and logistics
- Extensive planning for crane picks



Unique Construction Considerations and Mitigation

- Utilities (gas, electric, cable lines, sewer, water)
- Fuel oil back-up
- Tall Structures Demo
- **Traffic**
- Campus event planning
- Crane size optimized for scope of work and logistics
- Extensive planning for crane picks



Unique Construction Considerations and Mitigation

- Utilities (gas, electric, cable lines, sewer, water)
- Fuel oil back-up
- Tall Structures Demo
- Traffic
- **Campus event planning**
- Crane size optimized for scope of work and logistics
- Extensive planning for crane picks



Unique Construction Considerations and Mitigation

- Utilities (gas, electric, cable lines, sewer, water)
- Fuel oil back-up
- Tall Structures Demo
- Traffic
- Campus event planning
- **Crane size optimized for scope of work and logistics**
- Extensive planning for crane picks



Unique Construction Considerations and Mitigation

- Utilities (gas, electric, cable lines, sewer, water)
- Fuel oil back-up
- Tall Structures Demo
- Traffic
- Campus event planning
- Crane size optimized for scope of work and logistics
- **Extensive planning for crane picks**



Efficiency in Execution

- Elimination of waste through innovative Lean processes
- Repurposed many materials to add value to the project
- New gas boilers boosted plant's capacity by 80 percent (900,000 #/hr steam vs 500,000 #/hr steam)
- Efficiency in communication required between project players
- Smooth transition to operations



Efficiency in Execution

- Elimination of waste through innovative Lean processes
- Repurposed many materials to add value to the project
- New gas boilers boosted plant's capacity by 80% (900,000 #/hr steam vs 500,000 #/hr steam)
- Efficiency in communication required between project players
- Smooth transition to operations

Project is seeking LEED Gold certification

Lessons Learned

- Use ILPD processes to keep everyone “in the know” of each other’s work, and accountable as a team player
- Work with plant personnel to make sure buy-in is early on and continue to verify often
- In clustered urban settings, plan logistics every day
- Keep a cross function/cross party management team for rapid decision-making
- Establish contingency budgets early, and who manages
- Build consensus plan with all interested parties before committing to price
- Deploy “just in time deliveries” where at all possible



Questions

