

# Commissioning Challenges for a Military Microgrid

IDEA Campus Energy 2018

# PRESENTATION AGENDA

---

## NSF Indian Head Microgrid

- Project Overview
- Commissioning
- Issues Found in Operation
- Recommissioning
- Recap



Matt Klebosky, PE  
[mklebosky@wileywilson.com](mailto:mklebosky@wileywilson.com)

# PROJECT OVERVIEW

## Primary Design Objectives

- Maintain Steam Production and Critical Load
- Support Grid-Connected & Islanded Modes


Requires Coordinated Automation and Protection Systems

## Automation

- Control Operation Modes
- Prioritized Load Shed/Load Add
- Load Sharing

## Protective Relaying

- Typical Equipment Protection
- Utility Interconnection Requirements
- Island Detection





# AUTOMATION

Thursday, January 26, 2017  
10:29:03 AM

**iem** Power Systems™

**PRIORITY**

**1920 FEEDER**

FEEDER	1920-F1D	1920-F2D	1920-F3D	1920-F4D	1920-F5D
PRIORITY	3	2	1	6	8
STATUS	ADDED	ADDED	ADDED	ADDED	ADDED
MANUAL CONTROL					

FEEDER	1920-F6D	1920-F7D	1920-F8D	1920-F9D	1920-F10D
PRIORITY	7	4	8	5	9
STATUS	ADDED	ADDED	ADDED	ADDED	SHED
MANUAL CONTROL					


  

FEEDER	1920-F11D	1920-F12D	1920-F15D	1920-F16D
PRIORITY	9	9	9	9
STATUS	SHED	SHED	SHED	SHED
MANUAL CONTROL				

MAIN SYSTEM NETWORK SYSTEM ONLINE 780 ONLINE 1920 ONLINE STR ONLINE STRL ONLINE 1920 GEN STR GEN STRL GEN SYSTEM CONTROL PRIORITY

## 13.2kV System Configuration


- Two 69-13.2kV Substation Transformers
- Two On-site Generation Locations
- Two 2.5MW Standby Generators
- One 4.6MW CTG/HRSG



# COMMISSIONING

## August 2015

- Could not Affect the Facility Loads. Test Arrangement was Not Final Arrangement
- Connected One 6.4 MW and One 4.2 MW to B1920 Switchgear to Simulate Facility Load
- Found and Repaired Wiring Issues
- Functional Test Plan Based on the Sequence of Operations Document
- Performance Tests Focused on Gas Operation



**Phasor Diagram**

# ISSUES FOUND IN OPERATION


---

## SYSTEM HAS BEEN OPERATING FOR OVER TWO YEARS

In this time the Client has reported any item that they see as a potential system issue allowing the team to provide guidance on the cause, implement corrections and advise on operation issues.


- False Breaker Failure
- Generation Assets Not Coming On-Line
- Fuel Oil System Shutdown
- CTG Tripping After a Loss of Utility

# ISSUE: BREAKER FAILURE



**UNINTENDED BREAKER  
FAILURE INITIATE SIGNAL**






# ISSUE: FUEL OIL SHUTDOWN



## Solution


Identify Fail Safe Control Components and Supply them from a UPS Source

# ISSUE: FUEL OIL SHUTDOWN



Distribution System Faults Caused  
Fail Safe Relays Involved in Fuel  
Oil System Protection to Drop Out  
Triggering the Emergency  
Shutdown


# ISSUE: SYSTEM RECOVERY



**NO SYSTEM RECOVERY ON  
REVERSE OVERCURRENT TRIP**

# ISSUE: CTG SHUTDOWN

## CTG TRIP ON LOSS OF UTILITY WHILE ON FUEL OIL




Short Description	Line	Blue Value	Red Value	Delta
Unit 1.AN_Max_Fuel[kW]		20,486	20,536	50.07
Unit 1.ST_kW_Max_Lim_Active		0.00	0.00	0.00
Unit 1.AN_Ngp[%]		99.97	100.0	0.0301
Unit 1.AN_T5_Average_Temperature[°F]		1,250	1,251	0.250
Unit 1.AN_Pcnt_Load[%]		93.13	92.96	-0.168
Unit 1.ST_Util_CB_Closed		1.000	0.00	-1.000
Unit 1.AN_Engine_Pcd[psig]		130.6	130.9	0.331

<input type="checkbox"/> KF_Wf_Max_Fuel_Xn.Val		{...}	PCD
<input type="checkbox"/> KF_Wf_Max_Fuel_Xn.Val[0]		0.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Xn.Val[1]		20.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Xn.Val[2]		40.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Xn.Val[3]		60.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Xn.Val[4]		160.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Yn.Val		{...}	Wf_Max_kW
<input type="checkbox"/> KF_Wf_Max_Fuel_Yn.Val[0]		1759.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Yn.Val[1]		4561.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Yn.Val[2]		7026.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Yn.Val[3]		9800.0	
<input type="checkbox"/> KF_Wf_Max_Fuel_Yn.Val[4]		24940.0	

PCD 130.6 / 20,536 wF\_Kw @ UT-CB OPEN






# RECOMMISSIONING


## How did we prove the proposed updates work as intended?

- Develop and implement a test plan
- Utilize realistic and varying loading conditions
- Test occurred on actual system arrangement



# RECAP

- Identified single points of failure that caused the system to drop offline.
  - Cable Interference
  - Fail-Safe Signals
- Identified and corrected automation modes that prevented recovery.
- Improved CTG isolation strategy to allow for faster recovery.



# Q & A

Commissioning Challenges  
for a Military Microgrid  
IDEA Campus Energy 2018