

The Art of Replacing Boilers and Chillers in a Central Plant Without Impact to Production Needs


CampusEnergy2018 Conference Jay Ehrfurth-PE

BOLDT®

PLANT SITE OVERVIEW

NORTH PLANT

WEST PLANT



EAST PLANT

MRMC STATISTICS

MILWAUKEE REGIONAL MEDICAL CENTER THERMAL

- >7,500,000 square foot of conditioned space
- > 22 buildings from 5 customers
- > Approximately 2 miles of steam and chilled water lines > Approximately 2,500 feet of tunnel Peak chilled water demand – 18,000 tons > Peak steam demand - 205,000 lbs/hr. \succ Largest chilled water line = 42" HDPE and 36" PCCP > Largest steam line = 24" 15 psi and 12" 135 psi

PROJECT OVERVIEW

• **SCOPE:** Total removal of all assets associated with coal combustion and permanent replacement with gas/oil fired boilers. Replacement of steam driven assets and replaced with electric driven equipment. Addition of chillers and demo of older absorption chillers. New electrical feed to plant and internal distribution. Separation of steam and chilled water systems into two distinct plants.

• **BUDGET:** \$93,340,000

• SCHEDULE: Started spring of 2016 with projected completion fall of 2018



PROJECT & DESIGN PHILOSOPHY

Aspirations for a Steam and Chilled Water Future Redundancy

A second plant to provide continuous supply of critical thermal service with geographic source diversity, on site alternate fuel backup

Reliability

Investment in plant and distribution infrastructure to enhance uninterrupted, consistent source of thermal service

Environmental

Reduce noxious emissions through elimination of coal

Growth

Creating capacity for growth including and beyond the new Center for Advanced Care at Froedtert & The Medical College of Wisconsin POB

DECISION AXIOMS

- What is best for Owner (50 year solutions)
- Minimize any event that reduces reliability of utility production
- Incurred costs shall be spent wisely
- Understand if schedule impacts can be minimized
- Look for "Best use of space"
 - Operations Accessibility and location
 - Maintenance Footprint area around equipment, headroom, rigging access and aisle/openings for ingress and egress

DECISION MATRIX FOR SEASONAL ACTIVITY



• STEP 1

Work with an engineering consultant and Owner to develop clear definition around needs and options when removing existing equipment from service.

• STEP 2

Understand when new equipment can be tested and started up based on plant capacity to support needed loads on new equipment as well as loads on the plant at that time.


• STEP 3

Work with Owner to implement the chosen approach so new equipment can be commissioned under all load conditions, that the plant is never placed in jeopardy and plant assets are not overburdened, i.e. operational staffing.





STEAM = N+1 CHART



STEAM PRE-PROJECT CONDITIONS


- Boilers 1-3 (1955) Coal-Fired
- Boiler 4 (1970) Gas-Fired

Administratively limited for runtime

• Boiler 5 (2009) – Gas-Fired

Retain for continued use

Capacity	Pct	Age
255,000 lb/hr	63%	~60 yrs
80,000 lb/hr	20%	~45 yrs
67,500 lb/hr	17%	~10 yrs



> Boiler MACT was looming > NOx compliance is an issue

STEAM PRE-PROJECT CONDITIONS

	Capacity	
Peak Steam Load	Current Configuration	
242,000 lb/hr	Boiler 1 – 85,000 lb/hr Boiler 2 – 85,000 lb/hr Boiler 3 – 85,000 lb/hr Boiler 4 – 80,000 lb/hr Boiler 5 – 67,500 lb/hr	COAL COAL COAL NATU 600ps

Total Capacity (N+1) – 402,500 lb/hr Firm Capacity – 317,500 lb/hr

L JRAL GAS si Remains

STEAM POST-PROJECT CONDITIONS

	Capacity	,
Peak Steam Load	Current Configuration	
205,000 lb/hr	Boiler 15 – 70,000 lb/hr Boiler 16 – 70,000 lb/hr Boiler 21 – 70,000 lb/hr Boiler 22 – 70,000 lb/hr Boiler 5 – 67,500 lb/hr	NATU NATU NATU NATU

Total Capacity (N+1) – 347,500 lb/hr Firm Capacity – 277,500 lb/hr



RAL GAS/OIL **RAL GAS/OIL** RAL GAS/OIL **RAL GAS/OIL RAL GAS**

NEW RENTAL BOILERS STEP 1




DEMO OF COAL BOILERS STEP 2





INSTALLATION OF NEW GAS/OIL PACKAGE BOILERS STEP 3






INSTALLATION OF NEW GAS/OIL PACKAGE BOILERS STEP 3







CHILLED WATER = N+1 CHART



CHILLED WATER PRE-PROJECT CONDITIONS

Capacity	
3,750 tons	
4,660 tons	
0 tons	
4,820 tons	
6,850 tons	

Pct 19% 23% 0% 24% 34%

Age >25 yrs 20-25 yrs 15-20 yrs 10-15 yrs <10 yrs

ELECTRIC MOTOR DRIVEN 64%

> Significant age >Absorption technology inefficient, less reliable

ABSORPTION 27%

STEAM TURBINE DRIVEN 9%

CHILLED WATER PRE-PROJECT CONDITIONS

	Capacity		
Peak Chilled Water Load	Current Configuration		
16,800 tons	Electric Chillers (8) – 13,390 ton Steam Turbine Chillers (1) – 1,890 Absorption Chillers (5) – 4,800 to		

Total Capacity (N+1) – 20,080 tons Firm Capacity – 17,560 tons



ns tons

ons

CHILLED WATER POST-PROJECT CONDITIONS


	Capacity
Peak Chilled Water Load	Current Configuration
18,000 tons	Electric Chillers (8) – 13,390 ton Steam Turbine Chillers (1) – 2,070 Absorption Chillers (3) – 7,500 to

Total Capacity (N+1) – 22,960 tons Firm Capacity – 20,460 tons

ns tons

ons

CONSTRUCT NEW AREA FOR CENTRIFUGAL CHILLERS STEP 1



INSTALLATION OF NEW CENTRIFUGAL CHILLERS STEP 2







DEMO OF ABSORPTION CHILLERS STEP 3



PROJECT MANAGEMENT TOOLS – MILESTONE SCHEDULE

t ID	Activity Name	Remaining Duration	Start	Finish	Predecessors '	2018 Sep. Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep (
Milestones		228d	09-Oct-17	31-Aug-18		
*		228d	09-Oct-17	31-Aug-18		
Miscellaneous		228d	09-Oct-17	31-Aug-18	A CONTRACTOR OF A CONTRACTOR OFTA CONTRACTOR O	
A1690	West Plant WE Energize MV Switchgear #1A & #2A	51d	09-Oct-17*	20-Dec-17		West Plant WE Energize MV Switchgear #1A & #2A
A2570	East Plant Energize Switchyard Line #1 To Section #1 MV S	witchgear 3d	01-Nov-17*	03-Nov-17		 East Plant Energize Switchyard Line #1 To Section #1 MV Switchg North Plant BOILER Mechanical Completion - Full Release to Star
A2620	North Plant BOILER Mechanical Completion - Full Release	to Start Up Od	ICHIOLAGUESHINGE COULD	02-Nov-17	A1560	
A2580	Energize Switchyard Line #2 To Section #2 MV Switchgear	20	21-Dec-17*	22-Dec-17		Energize Switchyard Line #2 To Section #2 MV Switchge
JC-GN-MS-0025	InField Mechanical Completion	Od		07-Feb-18	JC-CN-IF-0150, JC-CN-IF-0130, JC-CN-IF-0060, JC-CN-IF-0020,	 In Field Mechanical Completion
JC-GN-MS-0060	West Plant Mechanical Completion - Boiler Complete	Od		15-Feb-18	JC-CN-WP-0470, JC-CN-WP-0340, JC-CN-WP-0340,	 West Plant Mechanical Completion - Boiler (
A2610	Turbine Hall Relocate EGE Offices & Utilities To Release D	emo 15d	01-Mar-18*	21-Mar-18	IC ON SUD OLOO	Turbine Hall Relocate EGE Offices &
A2650	West Plant Mechanical Completion - Chillers Complete Co	mplete Od		15-Mar-18*	JC-CN-WP-0470, JC-CN-WP-0340,	 West Plant Mechanical Completion - C
A2630	Water Treatment Mechanical Completion	Od		02-Apr-18*	JC-CN-NP-0410, JC-CN-NP-0390,	 Water Treatment Mechanical Comp
JC-GN-MS-0090	North Plant Mechanical Completion	Od		16-Apr-18*	JC-CN-NP-0170, JC-CN-NP-0150,	 North Plant Mechanical Completion
JC-GN-MS-0070	East Plant Mechanical Completion	0d		18-Apr-18	JC-CN-EP-0500, JC-CN-EP-049	 East Plant Mechanical Completion
JC-GN-MS-0100	Jamar DeMobilize Off-Site	16d	19-Apr-18	10-May-18	JC-CN-NP-0230, JC-GN-MS-0070	Jamar DeMobilize Off-Site
A2640	Turbine Hall Work Complete	DO		19-Jul-18	A1120,A1130,A1140,A1150	◆ Turbine Hall
JC-GN-MS-0110	Substantial Completion	0d		31-Aug-18*	JC-GN-MS-0070	Sub
Procurement		85d	02-Oct-17	01-Feb-18		
East Plant		37d	16-Oct-17	08-Dec-17		
Equipment - East P	lant	37d	16-Oct-17	08-Dec-17		
JC-PR-EP-0090	Receive Condensate Pumps (CDP-11 & 12, CDT-11 & 12)	D0		16-Oct-17*		 Receive Condensate Pumps (CDP-11 & 12, CDT-11 & 12)
JC-PR-EP-0100	Receive Condensate Tank (CD-TNK-11)	b0		06-Nov-17*		 Receive Condensate Tank (CD-TNK-11)
A2600	Receive Air Compressor	b0		08-Dec-17*		 Receive Air Compressor
West Plant		16d	02-Oct-17	23-Oct-17		
Equipment - West F	Plant	16d	02-Oct-17	23-Oct-17		
JC-PR-WP-0180	Receive Compressed Air Dryer (DRYR-21)	DO		02-Oct-17*		Receive Compressed Air Dryer (DRYR-21)
JC-PR-WP-0080	Receive Heat Exchanger (BX-21) (In Design)	DO		02-Oct-17*		🔶 Receive Heat Exchanger (BX-21) (In Design)
JC-PR-WP-0050	Receive Chilled Water Pumps (CHP-24, 25 & 26, ADSP-21) Od		23-Oct-17*		 Receive Chilled Water Pumps (CHP-24, 25 & 26, ADSP-21)
JC-PR-WP-0070	Receive Air / Dirt Separator Pump (ADSP-21)	Od		23-Oct-17*		 Receive Air / Dirt Separator Pump (ADSP-21)
North Plant		0d	02-Oct-17	02-Oct-17		
Equipment - North	Plant	Od	02-Oct-17	02-Oct-17		
JC-PR-NP-0010	Receive Condensate Polisher (POL-11)	DO		02-Oct-17		 Receive Condensate Polisher (POL-11)
JC-PR-NP-0020	Receive Water Softener (SFT-11)	b0		02-Oct-17		 Receive Water Softener (SFT-11)
JC-PR-NP-0030	Receive Reverse Osmosis (RO-11)	DO		02-Oct-17		🔶 Receive Reverse Osmosis (RO-11)
JC-PR-NP-0040	Receive Brine Tank (BR-TNK-11)	0d		02-Oct-17		Receive Brine Tank (BR-TNK-11)
JC-PR-NP-0050	Receive Make-up Water Tank (DI-TNK-11)	0d		02-Oct-17		Receive Make-up Water Tank (DI-TNK-11)
	Receive Treated Water Pump (DIP-11 & 12)	DO		02-Oct-17		Receive Treated Water Pump (DIP-11 & 12)
JC-PR-NP-0070	Receive Chem Feed System	Od		02-Oct-17		 Receive Chem Feed System
JC-PR-NP-0100	Receive Brine Transfer Pump (BRP-11)	0d		02-Oct-17		 Receive Brine Transfer Pump (BRP-11)
Infield / Pump Hous	se	85d	02-Oct-17	01-Feb-18		
Equipment - Infield		85d	02-Oct-17	01-Feb-18		
roject ID: MRMC Plant lech ata date: 02-Oct-17 un date: 09-Oct-17	TASK filter: % Complete less than 100. Layout:MRMC Master	Milwaukee F		edical Cente lule as of 0	er - Mechanical Project 9-Oct-17	Page 1 of 18

PROJECT MANAGEMENT TOOLS – PULL PLANNING



LESSONS LEARNED FROM **PROJECT IMPLEMENTATION**

- Use Integrated Lean Project Delivery® (ILPD) processes to reduce waste and keep everyone "in the ٠ know" of each other's work, and accountable as a team player
- Involve trade partners as early as possible, manage buy-outs with best quality for the project and not just short term gains
- Keep a cross function/cross party management team for rapid decision-making
- Look at equipment load profiles to take advantage of current capacities or optimize operations
- Use seasonal operation evolutions for phased construction approaches
- Establish contingency budgets early, and who manages
- Establish communication matrix to address key people and/or positions for information dissemination and timing of interactions
- Establish an approval/permit matrix and understand when, who, how and why in order to maintain a continuous project flow.
- Integrate operations and maintenance into the project early for smooth transition at turnover
- Seek simple solutions...the advantages will amaze you