



# ‘Efficient Energy for Smarter Cities’



A long-exposure photograph of the Dubai skyline at night. The Burj Khalifa is the central, tallest structure, illuminated with blue and white lights. The surrounding city is a dense cluster of skyscrapers, many of which are lit up with various colors like blue, green, and red. In the foreground, a complex highway interchange is visible, with light trails from cars creating a sense of motion. The overall scene is a vibrant, high-angle view of a modern metropolis.

# Delta T Syndrome, Why & How?

10<sup>th</sup> December 2018



Built to Last

DELTA  
DISTRICT COOLING



**“Sustainability is our top priority”**

: His Highness Sheikh Mohammed Bin Rashid Al Maktoum



Here today for


1. Present case studies- Delta T optimization.
2. What is the impact of Delta T on Facilities / Buildings and District cooling Plants.
3. How 'Delta' as a company is helping operate energy efficient smart cities?



## Impact of Delta T

- Inefficient use of chilled water system, draining the benefits of district cooling system itself.

- Higher electrical consumption at the District cooling plant
- Higher electrical consumption at the secondary side / due to over pumping of chilled water.
- Higher equipment life cycle cost







## Typical causes of Delta T

- Inadequate / wrong control logic.
- Wrong Index point selection and its set point, generally not evaluated using Hydronic model.
- Lack of proper commissioning.
- Un-calibrated/ non-operational flow control valves.
- Operators / user education.
- Change of design especially in 'Shell & Core' building arrangement.
- Design issues, lack of provisions for a proper counter checks.










## Due Diligence - Delta T


- Project : Residential & Offices
- Cooling capacity : 9,900 TR.
- Location : Dubai.
- Developer: NDA.
- Status : Study completed.



- The overall **Delta-T** on the secondary side was low as compared to the design **Delta-T** of 9.0°C.
- The supply temperature on the secondary side was higher compared to the primary side.




## Design review – Chilled Water Flow




- As per the load profile, additional Chilled water was being pumped compared to the corresponding design flow required.
- The extra flow pumped in BB06 (107%) & BB07 (98%) was very high.



### B06 FAHU 01



### R07 FAHU02



Buildings	Load as per heat load calculation (TR)	Load based on cooling area(TR)	Capacity of HEX connected (TR)
BB01	567.11	508.00	1462
BB02	521.2	481.34	1142
BB03	398.11	386.20	876
BB06	253.88	234.81	990
BB07	417.47	386.34	1080
BB10	272.54	240.51	982
BB11	345.10	317.39	1028
BB12	477.08	433.54	1074
BB13	447.53	434.30	1300

**Delta  
T**

**Cost  
Savin  
gs**




Operating the chilled water system as per design conditions of the building by manual changes on pumps and control valves.







## Flow Trend Pre-Simulation




## Flow Trend Post-Simulation



### Delta T Pre-simulation



### Delta T during Simulation



- Index circuit is the FAHU-BH-R-1 located on the roof.
- Existing location of DP switch is valid.
- Recommended index point set-point value is 93.7 kPa.
- Recommended pump head value is 317 kPa.




## Due Diligence & Implementation

- Project : Mixed use development
- Cooling capacity : 12,000 TR.
- Location : Abu Dhabi.
- Status : Fine tuning.




## Operating Delta-T



- The overall Delta-T on the main ETS was 3.42<sup>0</sup>C.



## History Chilled Water Flow




- As per the load profile, additional Chilled water was pumped compared to the corresponding design flow required.
- The extra flow pumped on the main ETS was 149% compared to the design flow.




1. Controls logic.
2. Non-industrial grade pressure transmitters.
3. Integration of PT with CHW pumps.
4. Bypassed flow control valves.
5. Lack of CHW balancing provisions.
6. Lack of standard operating




### Flow Trend Pre & Post -Implementation







## DPT fuction test





## How is Delta helping operate energy efficient smart cities



1. Lowering the energy consumption on secondary side pumping system.
2. Improving the efficiency of DCPs by ensuring they get the correct return water temperature.
3. Overall cost savings for all stake holders by optimized use of chilled water.



## Delta Vision & Mission



“Head quartered in the world’s most iconic smart city, Dubai, Delta is adding value to the **Sustainability goals** by staying **True** to our **Values** and being **INTELLIGENTLY DIFFERENT.**”

CEO,  
Delta District Cooling Services.

شكرا

Thank you!

Appreciate your  
patience.....!