



ETS Automation Verification

Taha Fahim

Control and Instrumentation Supervisor

Empower

Agenda

- ▶ Introduction
- ▶ The Current Situation
- ▶ Functional Check Objectives Flow chart
- ▶ A Typical ETS Setup
- ▶ Result
- ▶ Outcomes
- ▶ Discussion and Questions

Introduction

- ▶ We are responsible for ensuring supply of chilled water to our clients in a reliable and efficient manner by ensuring correct functioning of all of the Control & Instrumentation Systems.
- ▶ We maintain, calibrate, program, configure, test and upgrade our systems as necessary in ensuring the above.
- ▶ We implemented a new program which verify our control and instrument system remotely from Local SCADA in our District Cooling Plant or Command and Control Center.




The Current Situation

- ▶ Currently Empower supplies chilled water to around 1000 building each building is connected to the chilled water network through ETS.
- ▶ A proper functioning of ETS equipment are important to ensure efficient cooling and correct billing.
- ▶ We carry out calibration verification checks of the instruments connected to BTU meter so as to ensure correct billing.
- ▶ Visiting each ETS room and checking HEX sequence of operation which required time, manpower and transportations.
- ▶ We have implemented further functional checks to meet our customer requirements in a reliable way. We explain this as we move forward.

Functional Check Objectives


- ▶ To check whether Header return / HEX return Temperature sensors functions
- ▶ To check whether the configuration between flow meter and BTU meter are correct.
- ▶ To check whether the pressure across the ETS is efficient to give contractual flow
- ▶ To check the flow setting of each PICV
- ▶ To check the stem time travel of each PICV
- ▶ To check whether the flow velocity are with in the measuring range of the flow meter

A Typical ETS Setup




Flow Chart

- Close all HEX PICV
- Test begin on HEX1 by opening PICV 1 to 100% then 75%, 50%, 25%, close
- Same steps will be carried on HEX2.
- In each step we are recoding the Flow, Temperature and Valve Travel time values.
- This process take 30 minutes per HEX.
- Any abnormality in the process will be recoded in the report.



Result



Outcomes

- ▶ Temperature Sensors verification.
- ▶ PICV Valve configurations verification against the flow & pressure requirement
- ▶ PICV Valve opening times verification.
- ▶ Contractual Flow verifications
- ▶ On demand testing and verification.
- ▶ Historical logs keeping results for future reference.
- ▶ Remote testing(not required to visit each ETS room).
- ▶ Ensuring a fully functional ETS.

Discussions and Questions

Thank You

