Equipment Upgrades in a Space-Constrained Plant: University of Rochester Boiler Installation



Presented By: Rich Gardner (University of Rochester) Shane Taylor, P.E. (Sega Inc.)




International District Energy Association Campus Energy Conference 2017



Goal of Presentation

Provide a case study of how the University of Rochester and Sega worked together to install a boiler into the middle of an existing plant.



Project Background



Placement Considerations

Disadvantages

- New stack
- Uses valuable real estate
- Limits plant access
- Removes temporary boiler
 option

Advantages

- Easiest placement
- No demo required
- Enclosure required



Disadvantages

- Difficult move-in (obstacles)
 - Chiller
 - Two walls
 - Conduit chase
- Existing boiler demo required
- Limited indoor space


Advantages

- Better operator access
- Preserves outside space
- Preserves temporary boiler option
- Opportunity to remove harmful materials



Placement Decision: Indoor

- Lowest evaluated cost option
- Best long-term plant flexibility
- Allowed for optimizing internal space



Challenges for Indoor Boiler Option

Existing asbestos-filled boiler in way



Previous study confirmed asbestos construction:

- ✓ Boiler insulation
- ✓ Breeching
 - Piping
- ✓ Ash hoppers

24" cooling tower water piping in way [





Challenges for Indoor Boiler Option

Obstacles for move-in:




- 1. Exterior glass wall
- 2. Existing chiller
- 3. Interior CMU wall
- 4. Conduit chase
- 5. "Minor" obstacles





Challenge Solutions

Challenge	Solution
Limited Space	 Utilize an O-Style Boiler to best fit space Perform layout design in a 3D environment (scans) Top-down construction





Challenge Solutions

Challenge	Solution
Asbestos / Demolition	 Address schedule/budget for abatement and removal Simplify new install through re-use of existing infrastructure Floor design to best accommodate new boiler (open hole)



Challenge Solutions

Challenge	Solution
Move-in	 Remove unnecessary infrastructure (side benefits) Optimize timing for exterior wall removal/replacement Prepare "move-in" opening – deciding factor on overall boiler size Shoring to support floor Communication and planning with other campus divisions



Outcome

- Construction substantial completion 09/30/2016
- Startup / tuning / commissioning completion 11/16/2016
- Performance and emissions testing completion 11/25/2016





QUESTIONS?



