Campus Energy 2021 BRIDGE TO THE FUTURE Feb. 16-18 | CONNECTING VIRTUALLY WORKSHOPS | Thermal Distribution: March 2 | Microgrid: March 16



CHP Saves Lives: A Case Study of CHP on a Toronto Hospital Campus





Helping Our Clients Achieve Their Energy and Environmental Goals

Q&A Will Not Be Answered Live

Please submit questions in the Q&A box. The presenters will respond to questions off-line.


CHP Saves Lives: A Case Study of a Toronto Hospital Campus

Overview

- 1. Introduction
- 2. Combined Heat & Power (CHP) Project
- 3. Challenges
 - Technical
 - Non-technical
- 4. Critical Success Factors
- 5. Lessons Learned

February 2021

TRICT ENERGY







Sunnybrook Health Sciences Centre



- Largest Trauma Centre and largest Veterans Centre in Canada
- Teaching, Research, Brain Sciences, Heart, Cancer, Women & Babies (high-risk neonatal), Veterans
- 1.3 million patient visits per year
- 7-16 MW Electrical Load (4-5 MW emergency)
- 100,000 lb/hr steam peak,
 125 psig

February 2021







The Catalyst



- Feasibility studies, energy/cost savings, capital incentive
- Ice storm in December 2013
- Two years of freezing rain hit the city within two days
- 300,000 customers in Toronto without power
- Both supply feeders to Sunnybrook interrupted for 39 hours
- Emergency generator issues, precautionary NICU evacuations

What provides backup to the backup to the backup?



February 2021

Energy Supply Resiliency Projects



- Emergency Generator Plant Renewal 4 x 2 MW Diesel Generators
- Load Management System (LMS)
- 27.6 kV Substation Renewal
- Utility Feeder Upgrade (dedicated underground)
- Fuel Oil Storage Relocation/Upgrade
- Combined Heat and Power (CHP)
- Boiler Renewal (future)

February 2021

• Battery Energy Storage (BES) (future)





CHP Project Description - Overview




- New CHP Building, connected to existing Central Utilities Building
- Gas Turbine Generator (GTG), Natural Gas, Nominal 8 MW, 13.8 kV, inlet air cooling (chilled water)
- Heat Recovery Steam Generator (HRSG), 90,000 lb/hr, 130 psig, duct burner, provision for future condensing economizer
- Deaerator

February 2021

- Fuel Gas Booster Compressor (FGBC), 60-170 psig to 385 psig, outdoor acoustic enclosure, after/oil coolers
- Generator Step-Up (GSU) Transformer, 10 MVA, 13.8-27.6 kV
- Generator Breaker, 13.8 kV, 1200 A, revenue metering, generator protection
- 27.6 kV and 4.16 kV Substation Extensions



- 8







- 9 -












CHP Saves Lives: A Case Study of a Toronto Hospital Campus












- 12 -


















- 14 -








CHP Project Description - Schedule









CHP Project Description – Operating Modes



• Grid-connected

February 2021

Electrical load following
Minimum import limit
Export prohibited

• Islanding

Automatic (unplanned)
Manual (planned)
Intelligent load shedding
Black Start: Auxiliary load transfer scheme





Challenges

Technical Challenges

Complexity of many possible operating modes
Balancing redundancy, flexibility, simplicity
Integration with new and existing systems
Consideration/mitigation of failure modes

People Challenges

 \circ Permitting - Electrical Utility, Municipal, AHJ, Air & Noise

 \circ Overlap or lack thereof between projects, consultants, vendors, contractors









Technical Challenge – Supply Feeders

- Three (3) utility feeders supply the site:
 - Dedicated (new underground feeder)
 Alternate
 Backup (generation not permitted)
- Utility can closed-transition between all feeders without notice
- Only respond to transfer trip command from the connected feeder

How do we know what we're connected to?

NORMAL

BACKUP





ĒΜ


ALTERNATE

Technical Challenge – Bus Configuration CEM


- Campus load divided into A and B buses
- What if Bus A or B is out of service?
- Allow GSU to connect to both sides with interlock
- Single-bus operating mode: islanded or grid-connected
- Complex protection logic automatically identifies mode
- Generator can synchronize across three (3) different breakers



- 20




Connected to Utility A via Bus B











Connected to Utility A via Bus A











INTERNATIONAL DISTRICT ENERGY ASSOCIATION February 2021






Connected to Utility B via Bus A










Islanding Bus A, Utility B supplying Bus B







Technical Challenge – Switchgear Modifications

- New 27.6 kV substation project coordination
- Hardware modifications required for CHP

 Protection relay replacement
 Interlocks, remote control, sync check
- Modification to automatic transfer scheme

 Maintain transfer scheme while CHP offline
 Block transfer if CHP online









Technical Challenge – Emergency Generators CEM

- Minimize changes to essential electrical systems
- Ensure compliance with CSA Z32 Essential Electrical Systems in Health Care Facilities
- Auto-start and seamless transfer upon islanding

February 2021

 Prevent re-transfer to normal when islanding, especially black start







Technical Challenge – Load Management



- Response to grid interruptions must:

 Act immediately to avoid overload
 Maintain continuous supply to essential loads
 Minimize interruption to non-essential loads
 Prioritize between non-essential loads
- Integration with new Load Management System (LMS)
- Integration with existing breakers and chillers; limited documentation
- Continuous monitoring of load, generation, capacity; load shed table
- Prevent inadvertent auto-restart





People Challenge – Electrical Utility – Approvals



- Original connection application completed **in 2016**
- Consultations held at beginning of project early 2018

 New Dedicated Feeder
 Battery Energy Storage (BES)
- Revised application review time: 7 months
 Results received at end of design phase
- Requirements had to be anticipated from prior experience to maintain project schedule





- 29

People Challenge – Electrical Utility – Managing Change, Schedule

- Six months of design review and negotiations
- Frequent design modifications post-design phase

 Allowable operating modes/scenarios
 Protection logic, interlocks, transfer trip scheme
 New utility-owned automation controller
 SCADA points
 New fiber lines added to replace existing wireless
 - \circ New fiber lines added to replace existing wireless
- Minor changes continued through commissioning

February 2021







Critical Success Factors

- Building relationships and trust
- Relationship with electrical utility
- Collaboration between consultants, Start-up Engineer, Commissioning Agent
- Contractor working closely with equipment technicians
- Pre-selection of major equipment
- Consideration for failure modes

February 2021

• Thorough commissioning process







Lessons Learned – Utility



- Experience with local utility is essential
- Meet early and often regular contact throughout project
- Thorough documentation of discussions, decisions
- Schedule tracking and follow-up
- Minimize costly changes and delays

 Demonstrate expertise, build trust
 Provide justification of design concepts
 Understand constraints







Lessons Learned – Collaboration CEM

- Close integration of multiple projects
- Collaboration between consultants, owner, contractors, utilities, vendors
- Relationship between parties is foundational for success
- Demonstrate expertise with evidence
- Mutual respect and fairness

February 2021

- Share ideas, feedback, constructive criticism
- Project/customer success primary focus of all parties



Thank You!

For any questions, please contact:

Steve Quinlan, P. Eng. Manager of Electrical Engineering <u>steve@cemeng.ca</u> www.cemeng.ca







