### Microgrid Resiliency at Yale University

#### Sam Olmstead, Director of Utilities, Yale University

February 13, 2020



Yale office of facilities

A modern campus microgrid is incredibly complex, with many integrated components – generation, switchgear, protection and control, automation and SCADA, power distribution and building substations.

This complex physical infrastructure must be operated reliably and efficiently against a complex backdrop of campus operations, unpredictable weather, aging electrical grids, shifting academic priorities and constrained operating budgets.


#### Microgrid Resiliency Strategies

- Develop an operating philosophy for your system
- On new projects, build in reliability from the start
- Make your system as flexible as possible
- Take extra time and money to fully commission everything
- Use automation so "when the bad thing happens" stable operation is maintained

#### Yale University Microgrids


- 2 Sites Main Campus (Central Power Plant) and Medical School/Hospital (Sterling Power Plant)
- Each 15 MW with heat recovery and grid interconnection
- Primary Select Campus Distribution Circuits fed at 15 kV
- Sterling Plant converted to cogeneration in 2010
- Central Plant original cogeneration in 1997, repowered in 2016

#### Yale Central Power Plant Microgrid




Emergency Power: Local to building

### Operating Philosophy



#### Fast Bus Transfer – Stay on Grid

- Implemented via contact logic
- Enabled and supervised by Synch Panel PLC and local Synch Check
- Sequence:
  - 2 UI feeders trip (not Arc, Bus Diff, Bus O/C)
  - UI Breakers proven open
  - Main Tie breaker closes
  - GT Tie breaker stays open




#### Campus Load Shed – Keep Generation Running

- Uses electromechanical frequency-based load shed relays
- First installed with original cogen hardwired scheme:
  - Residential/Academic buildings shed first
  - Low Density Science/Academic next
  - High Performance Science last
- Made sense until October 29, 2012 Hurricane Sandy:
  - Load too high to Island
  - State of Connecticut travel ban
  - Yale University closed to non-essential personnel
  - Students told to shelter in their dormitories
  - One Problem: In the event of a loss of utility, these buildings would be the first to lose power!

#### Selectable Load Shed – Flexible Solution

- Load shed relay outputs rewired to local PLC-based controller
- Load shed lockout relays installed for each campus breaker
- Controller outputs to each LOR
- DCS Supervision of controller allows outputs to be reconfigured to different load shed levels as needed
- PLC refresh adds small amount of time; however, experience has been that the system works very well


### **Operating Philosophy**



#### Standardized Double-Ended Substation Design

# Double-Ended Substation with Auto-Throwover:

- Automatic system supervised by PLC
- Bus Undervoltage trips main and closes tie
- Inhibited on overcurrent, ground fault or arc detection
- Automatic retransfer after 10 seconds



# "Commissioning is a process that begins in design, continues through construction, and concludes with functional testing."


#### Cx Best Practices: Design

- Make sure you (as the owner) understand:
  - What your electrical system is and is not capable of especially the Protection and Control
  - What is required to enable this capability?
  - How will we test it to make sure?
- Design Considerations:
  - Have we included break points in the system, such at test switches?
  - Where will the load come from to test? How will it be connected to our system?
  - Do the project documents describe the full control philosophy? Do they include enough documentation to troubleshoot?

Construction QA is vital to functional testing going well:

- Validation of key inputs that are not "settings" per se such as PT and CT ratios
- CT polarity
- Documentation of control wiring between pieces of equipment (e.g., generator differential CT wiring to generator breaker relays)
- Relay I/O Mapping
- Interface to plant control system

#### Example: Show complete wiring path on Schematic



#### Cx Best Practice: Integrated Functional Testing

- Challenge as much of the protection circuit as possible
- Validate external outputs

   e.g. control system
   annunciation/SOE
- Be prepared to add to your test script on the fly

A. Phase A a. Initiate a "Phase A" 87 Bus Differential by injecting current A-Phase KAB Indicates pick-up .Check 86BD-A relay activated ..... ..Check 86BD-A2 relay activated..... ..Check SOE point in DCS ..... ...Check DCS Graphics Display ......Check Indicate Breaker trip on chart below. ---ISLOCK CLOSE 561 ON OFF ADARZ PRIM SNCOAM 3/3/16 1903 LOR TO DES 86 D 1 86B 86E | 86F OK OK OK CKICK CLOSE IN CONN. POS. BLOCK LOR \$6ARC-A 86BD-A/A1 26F 86H 1960/C-A 86D 86A | 26B S6E 1911 00 0-K OK OK 194 UK LOR BLOCK CLOSE IN COUN. PUS 1911 86 BD-A/A1 960/C-A 86 ARL-A Ø K ¢К 64 25V JUMPER HVTR-1 LOR BLOCKCLOSE IN CONN. POS. 86B 86C 46D

860/c-A 26

Feeder #1A (1903) Functional Testing, Rev. 3, 2/19/16



## Questions?



Yale office of facilities

Thank You!

#### Sam Olmstead Yale University samuel.olmstead@yale.edu



Yale office of facilities