



WAKE FOREST
UNIVERSITY



RMF Engineering
Reliability. Efficiency. Integrity.



Central Heating Plant Upgrade

February 2014




**Wake Forest University
District Utilities
Existing System
Project Goals
Project Overview
Efficiency Improvements
Projects Results
Q&A**



Private ACC School
Winston-Salem, NC
~5,000 Undergrads
~7,500 Total Students
Recent Growth

4 New Buildings
2.7 – 3.1 million s.f.
59/63 Buildings
3,400/3,880 Beds



- **Most Buildings Served By District Utilities**
 - **Steam – 121,000 pph Connected Capacity, Historical Min ~ 6,000 pph, Max - ~ 44,000pph**
 - **Electric – 20 MW (Duke Energy) Transformer, 13 MW Peak**
 - **Chilled Water – Campus Loop w/ 4 Plants, 6,700 Tons Capacity, 5,200 Tons Peak**
 - **Water/Sewer – Campus Loop, 2 Feeds From City**
 - **Stormwater – Two Primary Outfalls**



	Budget FY14
Steam	\$2,625,112
Electric	\$4,125,577
Chilled Water	\$1,237,234
Wtr/Swr	\$702,778
Storm Wtr	\$179,498
Total FY14	\$8,870,199






Figure II-5: Future Steam Distribution

Campus Loop

1.1 Miles in Accessible
Tunnels

95 psi Distribution

80% + Condensate
Return

Central Plant





2 – 1954 Erie City Boilers

- Ea. 50,000 lbs Steam/Hr
- Natural Gas & No. 2 Oil
- 1 Orig, 1 Retubed (1998)
- Boiler Controls Updated 2010

Plant Controls Updated 2006

Sub-Systems Mostly Original






- **Increase Steam Generation Capacity**
 - Campus Growth
 - Master Plan
 - **Eliminate or Minimize Annual May Steam Shutdown**
 - Increase Redundancy in Sub-Systems, Isolation Valves
 - **Renewal of Steam Generation Sub-Systems**
 - FCAP, Repair History, Useful Life, Code Compliance
 - **Improve Plant Efficiency**
 - Co-gen, New Technology, Boiler Efficiency
 - **Road Map for Steam Plant of the Future**
 - Possible Buildings (5 Years), 3% Growth Beyond 5 Years
-

Winter Peaks

65,000 – 70,000 pph

Summer Lows


10,000 – 15,000 pph



Master Plan Capacity Needs


Winter Peaks

95,000 – 105,000 pph





Solar - Mercury 50		
Electric Output	4,600	kW
Unfired Steam	13,800	pph
Installed Cost	\$ 15,768,000	
Annual Net Savings	\$ 409,434	
Year 1 ROI	3%	
Simple Payback	38.5	Yr



2 – 20,700 pph Boilers

- 1 in 2013, 1 in 3- 10 years

Redundant Sub-Systems

- Make-up Water, Condensate Tanks, Feedwater Pumps, Deaerator


New Control Room

Improve Sub-Metering

Improve Plant Efficiency

Code Compliance

Steam Plant Master Plan



DA Tank Condensate Return Tank Feedwater Pumps





ENERGY CONSERVATION MEASURES

WAKE FOREST UNIVERSITY - BOILER ADDITION

OPTION NO.	DESCRIPTION	ANNUAL ENERGY DATA		LCCA ECONOMIC METRICS	
		INSTALLATION COST (\$)	PLANT FUEL TO STEAM EFFICIENCY (%)	SIMPLE PAYBACK (YRS)	FIRST YEAR ROI (%)
	EXISTING PLANT		77.8%	---	----
BASE	2x 600 BHP FIRETUBE BOILERS (N+1) [41,400 PPH]	BASE	81.7%	---	----
1	TRADITIONAL FEED WATER ECONOMIZER	\$114,814	84.0%	3.8	26.2%
2	FW ECONOMIZER AND CBD HEAT EXCHANGER	\$204,874	84.5%	5.3	19.0%
3	CBD HX AND CBW FEEDWATER AND MAKEUP WATER ECONOMIZERS	\$281,157	85.5%	5.4	18.4%
4	CBD HX AND DCI FEEDWATER AND CONDENSATE ECONOMIZERS	\$800,160	85.8%	14.2	7.1%

- **Fully Metered Controls w/ O₂ Trim**
- **VFD Boiler Fan**
- **Continuous Blow-Down HX**
- **Flash Recovery**




Key Design Considerations


- Available Heat Sinks
- Direct vs Indirect Contact
- Make-Up Location
- Stack Materials
- Packaged vs Custom



Simple Indirect Cond. Econ. Pre-Heat Make-Up Water




Blr 3 vs Blr 2 % Eff Dec. 2013




- **Increased Steam Generation Capacity**
 - 20,700 pph + Retuned Ex Boilers
 - **Minimized Annual May Steam Shutdown**
 - Redundancy
 - Isolation Valves
 - Distribution Challenges Remain
 - **Renewed of Steam Generation Sub-Systems**
 - FCAP, Repair History, Useful Life, Code Compliance
 - **Improved Steam Plant Efficiency**
 - New Technology, Boiler Efficiency
 - **Road Map for Steam Plant of the Future**
 - Possible Buildings (5 Years), 3% Growth Beyond 5 Years
 - **Road Map the Future**
 - UOC – Utilities Operations Center
-

New Steam Plant Control Room
Utilities Monitoring
Campus BAS Monitoring
Off Hours Call Center







Wake Forest University

Winston-Salem, North Carolina

BCM-70
WE Btalk-75
NAE-100001
NAE-100010



- 1 North Campus Apts
- 2 Winston Hall
- 3 Salem Hall
- 4 South Residence Hall
- 5 South Chiller Plant
- 6 Welcome Center
- 7 The Barn
- 8 West Chiller Plant
- 9 WFDD Radio Station
- 10 North Chiller Plant
- 11 Farrell Hall

Outdoor Lighting
Lucid Dashboard
Energy-East/Central Campus
Energy-West Campus

To BB&T, Deacon Twr
To Off-Site Storage

OA Temp: 25.5 °F OA Humidity: 29.2 %RH OA Enthalpy: 8.8 BTU/lb OA CO2: 430 ppm Dev-32581 Jan 29, 2014 10:59 AM

ALARMS

Smoke Alarm: <input type="checkbox"/>	Fan Runtime Alm: <input type="checkbox"/>	Bad RAT Sensor: <input type="checkbox"/>
Freeze stat: <input type="checkbox"/>	Htg Coil EnergyWaste Alm: <input type="checkbox"/>	Bad Preht Sensor: <input type="checkbox"/>
H/L Static Press: <input type="checkbox"/>	Clg Coil EnergyWaste Alm: <input type="checkbox"/>	SAT Alarm Setpt: 8 °F
Comm Fail w/Aircuity: <input type="checkbox"/>	Clg Capacity Shortage Alm: <input type="checkbox"/>	Htg Coil SAT Alm Setpt: 8 °F
Filter Alm: <input type="checkbox"/>	Bad SAT Sensor: <input type="checkbox"/>	Freeze Prot. Alm Setpt: 35 °F
Comm Fail w/Global: <input type="checkbox"/>	Bad MAT Sensor: <input type="checkbox"/>	Freeze Prot Alm Reset: <input type="checkbox"/>

AREA STATUS

Occupied C m d: Occupied

Occupied: ● NHL: ● NLL: ●

Warm up: ● Afterhrs Ovr: ●

Cooldown: ●

# Of VAV Press Req: 3	3
# Of VAV Clg Req: 3	4
# Of VAV CO2 Req: 5	1

Farrell - AHU-5 VLC1

Serves North Crd Floor /Mech P...

Home
Previous

VLC Prop
AHU-3 VLC2
AHU-4 VLC2
AHU-5 VLC2
AHU-6 VLC2
AHU-7 VLC2
AHU-8 VLC2

DAMPER CONTROL

Economizer

Econo Favorable (Aircuity): ☐

Bldg Iso Dmprs Open: ●

Disable Economizer: ☐ Econo Mode: ●

MAT Signal: 0.0 %

Low MAT Econo Limit Signal: 100.0 %

Econo Max Pos. Setpt: 95 %

Econo OAT Lockout (Comm Fail): 60 °F

Force Economizer ON: ☐

CO2 Control

Disable CO2 Control: ☐ CO2 Mode: ●

Current Min OAD Position: 38.0 %

Min OAD Pos-Min Setpt: 11 %

Min OAD Pos-Max Setpt: 38 %

CO2 Dm pr % Bump Time: 0 min

CO2 Dm pr % Increment: 1 %


ERV Press Request: ●

Space Pressure (Relief Damper)

Space Pressure: 0.070 in. wc

Space Pressure Sig: 100.0 %

Space Pressure Setpt: 0.05 in. wc



RETURN AIR
Temp: 49.8 °F
Dewpt: 0.9 °F
CO2: 379 ppm

MA TEMP
MATemp: 46.2 °F
Current Setpt: 62.0 °F
MAT Diff Setpt: 3 °F

PREHT VALVE
Viv C m d: 64.9 %
HW Request: ●
Current Htg SA Temp Setpt: 60.0 °F
Htg Temp Diff Setpt: 5 °F
Htg Temp Low Lim it Setpt: 45 °F
Preht MAT Low Lim it Setpt: 45 °F

CHW VALVE
Viv C m d: 0.0 %
CHW Request: ●

DEHUMIDIFICATION

Disable Dehumid: ☐ Dehumid Mode: ●

Return Air Dewpt: 0.9 °F

Dewpt Setpt: 58 °F

Dehumid Signal: 0.0 %

Dehumid SAT Setpt: 65.0 °F

SAT Setpt-Low Lim it: 52 °F

SUPPLY AIR TEMP / PRESSURE

TEMP	Static Press
Temp / Press: 60.1 °F	1.49 in. wc
Current Setpt: 65.0 °F	1.50 in. wc
Setpt-Warm up: 75 °F	
Setpt-High Lim it: 65 °F	2.00 in. wc
Setpt-Low Lim it: 55 °F	0.50 in. wc
Setpt-Manual: 55 °F	2.00 in. wc
Setpt Mode: Auto	Auto
Reset Increment Setpt: 0.3 °F	0.10 in. wc
Reset Bump Time: 5 min	5 min

SUPPLY FAN

Disable Unit: ☐ In

C m d Status Alarm Hand: ● ● ●

Status Alm Reset: ☐

VFD Speed: 90.9 %

VFD Min. Speed: 20 %

Fan Runtime: 5685 hrs

Fan Runtime Alm Setpt: 10000 hrs

OA Temp: 24.7 °F

Dev-27100

S. Chiller Plant - VLX

Jan 29, 2014 10:54 AM

Comm Fail w / Salem Hall (OAT):

CT-1 Settings

Cmd Status Alarm

CT-2 Settings


Cmd Status Alarm

CT-3 Settings

Cmd Status Alarm
3A: 3B:

CT-4 Settings

Cmd Status Alarm
4A: 4B:



Home Previous
Chiller Staging
Miscellaneous
Sequence
VLX Prop

To Secondary Loop

Pri. Flow Rate
(GE Meter)
38 gpm


To SECONDARY
CHW PUMPS

FROM CAMPUS LOOP





 RMF Engineering
Reliability. Efficiency. Integrity.

 AC
CORPORATION
Established 1935



 I'LONG
CONSTRUCTION CO., INC.

 MARTIN
CONTROL
& Equipment Company

 Facility Dynamics
ENGINEERING

