

# Install Boiler 10 Natural Gas Burners

2014 IDEA Conference

February 19, 2014

Presented by:

Benjamin E. Anderson

P. Russell Price, PE

Kevin C. Voss, PE



THE UNIVERSITY  
OF IOWA



PRVN CONSULTANTS, INC.


- Introductions
- Plant Overview and Gas Burner Need
- Permitting Strategy
- Project Design
- Project Construction
- Startup and Lessons Learned
- Conclusion
- Questions

# Agenda

---

- University of Iowa – Main Power Plant
  - ✓ 4 Boilers: 600+ klb/hr, 3 Turbine Generators - 24.7 MW

Boiler	Installed	Fuel	Capacity	Emissions Control
7	1991	Gas	100,000 lbs/hour	Low Nox Burners
8	1991	Gas	100,000 lbs/hour	Low Nox Burners
10	1975	Coal	170,000 lbs/hour	Electrostatic Precipitator
11	1987: modified in 1996	Coal & Biomass	170,000 lbs/hour	Baghouse and SO <sub>2</sub> Emissions Control



- ✓ 6 offsite natural gas and 1 biomass boilers

## Overview

- Install two (2) new low Nox gas burners with individual air plenums in the existing pressure part openings.
- Install a new FD fan to support full-load natural gas firing.
- Install an FGR system for:
  - ✓ lowering natural gas burner NOx emissions.
  - ✓ Cooling the natural gas burners during stoker firing
  - ✓ Cooling the stoker grate during natural gas firing
- Install an airflow measurement device to measure combustion airflow to the natural gas burners.

## **Project Scope**

---

- Remove two (2) of the five (5) existing boiler ash hoppers and associated reinjection lines.
- Monitor the SH steam and metal temperatures during natural gas firing to prevent overheating of the superheater outlet header and superheater tubes.
- Protect the grate via gravel or by being bricked over if the University plans to fire solely natural gas. If stoker-firing capability is to be retained at all times, cooling air or cooling FGR can be passed through the stoker.

## **Project Scope (Cont.)**

---

<b>Parameter</b>	<b>Boiler 3</b>
Steam flow (lb/hr)	170,000
Steam temperature (°F)	760
Steam pressure (psia)	490
Feedwater temperature (°F)	360
Drum pressure (psia)	---
Superheat Attenuation	Yes
Original fuel	Coal
Firing arrangement	Traveling grate Spreader stoker
Superheat	Yes
Air heater type	Tubular


## **Boiler 10 Performance**

---


Fuel type	Natural gas
Fuel flow per burner	108,000 schf
Design heat release per burner	108 MM Btu/hr
Minimum heat release per burner	9 MM Btu/hr
Total boiler heat release	218 MM Btu/hr
Burner turndown required	12:1
Excess air at design heat release	10%
Combustion airflow per burner	25,314 ACFM

## **Burner Operating Data**

---



# P&ID of Boiler 10 Prework



# P&ID of Boiler 10 Post Work

- The existing FD fan does not have sufficient static pressure capability for full-load natural gas firing.
- A new FD fan is required for full-load natural gas firing.



## **New FD Fan**

---

<b>Design Criteria</b>	<b>Units</b>	<b>Test Block</b>	<b>100% Boiler MCR</b>
		<b>+10% Flowrate, +21% Static, +25°F</b>	<b>0% FGR Included</b>
Combustion airflow rate	lb/hr	189,200	172,000
Combustion air temperature	°F	275	250
Volumetric flow rate	ACFM	59,800	52,500
Total static pressure	iwc	14.5	11.9

## **Natural Gas FD Fan Sizing Criteria**

---



**One of Two New Gas Burners**

---

Flow	ACFM	59,800
Static Pressure	in. WG	15
Speed	RPM	1,780
Power	BHP	176
Temperature	°F	275
Elevation	feet	650
Density	lb/ft <sup>3</sup>	.0527
Outlet velocity	ft/min	3,902

## Natural Gas FD Fan Performance

---



**Breeching to the Burners was Modeled**

---

Parameter	Units	Boiler 3	
		Coal	Natural Gas
Flue gas inlet temp	°F	1,650	1,916
Flue gas outlet temp	°F	1,240	1,337
Steam inlet temp	°F	472	470
Steam outlet temp	°F	775	820
Calculated tube midwall temp	°F	827	902
Tube midwall temp limit	°F	1,017	1,017
Calculated tube outer wall temp	°F	829	<b>904</b>
Tube outer wall temp limit	°F	900	900

Changing FEGT, absorption effectiveness, and flue gas flow cause some pressure part temps to rise and some to fall.

## Tube Metal Temps & Pressure Part Mods

Parameter	Units	Boiler 3	
		Coal	Natural Gas
Load	%MCR	100	100
Type of attemperator station			Spray
SH temp before spray	°F	779	815
SH temp after spray	°F	755	760
Total superheat steam flow	lb/hr	159,485	170,000
Spray water temp	°F	352	352
Spray water flow	lb/hr	1,897	<b>4,671</b>


## Attemperator Flow

---




# **Superheater Tube Temperature Transmitters**

---




# Furnace Exit Gas Temperature (°F)

---



Data is at 100% MCR load.

## Combustion Air & Flue Gas Flow Rates (lb/hr)



# Total Boiler Losses on Efficiency (%)

---



## **New Breaching and Damper**

---



# **New Burner Fan**

---



# New Breaching

---



# New Flow Meter

---



# New Gas Train

---