

# Central Plant Commissioning

*Realizing Your Reliability and Efficiency Goals*

Presented by: Nick  
Rauth



# Agenda


- ▶ What is Commissioning?
- ▶ Why do I need it?
- ▶ Challenges of Central Plant Commissioning
- ▶ Case Studies
- ▶ Q&A




# What is Commissioning (Cx)?

- ▶ ASHRAE defines the Commissioning Process as “...a quality-oriented process for achieving, verifying and documenting that the performance of the facilities, systems, and assemblies meets the defined objectives and criteria.”
  - ▶ Simplified:
    - Commissioning (Cx) is a quality control and validation process for facility and facility systems’ construction
- or
- Process designed to ensure the finished facility operates in accordance with the documented owner’s project requirements

**NOT** just testing at the end!



# Commissioning Timeline – Level of Effort




# What is Driving the Need for Commissioning?

- ▶ Industry Changes
- ▶ Contract Complexity
- ▶ System Complexity
- ▶ System Reliability
- ▶ Energy Efficiency

Commissioning  
helps fill the gaps  
in coordination

Commissioning  
encompasses "All"



# How does Commissioning benefit projects (or more importantly....owners)?

- ▶ Establishes clear measurable goals and accountability
- ▶ Risk Mitigation
- ▶ SAFETY
- ▶ Energy savings
- ▶ Reduced change orders, claims and callbacks
- ▶ Improved documentation



# Central Plant Cx Challenges

- ▶ Coordination with Campus
  - Requires thorough design review
- ▶ Testing to Active Critical Loads
  - Requires coordination with Ops staff
  - Utilize plant loads (ie TES) where possible
- ▶ Balance of Plant Integration
  - Requires thorough submittal review
  - Hands-on coordination with Integrat
- ▶ Electrical Complexity
  - High Risk requires experienced oversight
  - Comprehensive coordination study is



# UKHA Vertical Expansion

Kansas City, KS

- ▶ 120,000 sf, 3 ½ story vertical expansion over the existing 6 story Center for Advanced Heart Care (CAHC) at The University of Kansas Hospital.
- ▶ CUP Expansion:
  - 2000ton Duplex Electric Centrifugal Chiller
  - 3000gpm Chilled Water Pump
  - 4000gpm Condenser Water Pump
  - Two Cooling Tower Cells
  - 2MW emergency generator





# UKHA Vertical Expansion Cx

## Cx Challenges

- ▶ Coordination between multiple control systems
  - Chiller/Chiller Staging: Trane
  - Pumps/Towers: Allen Bradley
  - BAS: Metasys (JCI)
- ▶ Existing Generator Undersized
  - Emergency generator not sized to meet load of new chiller
- ▶ Chiller Valve Timing Discrepancies
  - Duplex chiller valves coordination with compressor failure
  - Duplex chiller actuation time differed from existing chiller actuation time

## Solutions

- ▶ Detailed submittal review
- ▶ Close coordination with 3<sup>rd</sup> party Integrator
- ▶ Field verification of ladder logic
- ▶ Rewrote SOPs for the weekly generator load test
- ▶ Incorporated additional code into emergency shutdown sequence
- ▶ Modified shutdown logic to prevent choking flow to second compressor on failure of the 1<sup>st</sup> compressor
- ▶ Staging logic timing changes to ensure flow path maintenance

# University of Texas Hot Water Plant #1 & Chilling Station #7

Austin, TX

- ▶ EPC Project (Flintco/BMcD JV)
- ▶ BMCd provided Design, Start-up and Commissioning Services

## Installed Capacities:

- ▶ Hot Water: 62.5MMBTUH
- ▶ Chilled Water: 15,000 tons
- ▶ Thermal energy Storage: 5.5Mgal



## Features:

- ▶ Full Remote Operability
- ▶ Thermal Energy Storage
  - Integrates with existing TES tanks
- ▶ Designed for Future Capacity Expansion

# UT HWP#1 and Chilling Station #7 Cx

## Cx Challenges

- ▶ Multiple TES coordination
  - Existing TES-1
  - Pressure/Flow control switchover
- ▶ Lack of site load for system verification
- ▶ Relational Controls

## Solutions

- ▶ Hands-on support during start-up
- ▶ Detailed planning and review with Operations
- ▶ Review of existing ET and TES settings/control
- ▶ Phased/sequential testing
  - Dry run through logic and start-up with minimal load
  - Full load ramp up once site load is available
- ▶ Field testing to tune algorithm constants
- ▶ Field verification of control valve Cv curves

# FDA Research Center White Oak

## Silver Spring, MD



- ▶ Client: Honeywell
- ▶ Owner: GSA
- ▶ Tenant: FDA
- ▶ Original site of Naval Surface Warfare Center
- ▶ State of the art \$1.5B office, research and labs
- ▶ Existing: 3.9MM sqft
- ▶ Expansion: 1.1MM sqft
- ▶ Energy Savings Performance Contract (three separate task orders)


# Existing Central Utility Plant (ESPCII)



- Central Plant Construction
  - 20,000 sqft reconditioned space
  - 8,000 sqft new construction
- Central Utilities
  - 10,000 Tons Cooling
    - (2) 1,100-ton absorption chillers
    - (2) 1,130-ton and (3) 2,000-ton Centrifugal Chillers
  - 30 MMBTUH Heating
    - (3) dual-fuel 10 MMBTUH HW Boilers
  - 25.8 MW Power Generation
    - (4) 4.5 MW NG fired Solar Merc50s
    - (1) 5.8 MW dual-fuel reciprocating engine
    - (1) 2 MW standby diesel generator
- Thermal & Electrical Distribution



# New Central Utility Plant (ESPCIII)



- ▶ 50,000 sqft LEED® Silver facility
- ▶ Central Utilities
  - ▶ 7,500 Tons Cooling
    - (3) 2,500-ton Centrifugal Chillers
    - 2MM Gallon TES Tank
  - ▶ Heating
    - (1) 25 KPPH dual-fuel Steam Boiler
    - 112 MMBTUH heating HW converters
  - ▶ 29 MW Power Generation
    - (2) 7.5 MW dual-fuel Solar Taurus70s
    - (1) 4.5 MW NG fired Solar Merc50s
    - (1) 5.0 MW Elliott steam turbine
    - (2) 2.25 MW black start diesel generators
  - ▶ 12.5 MW E-gen for Critical Lab Loads
  - ▶ 80k gal Fuel Oil Backup
- ▶ Utility Distribution
- ▶ Campus Load Control



# Installed Capacity

- ▶ Power: 67MW from 17 Generators
- ▶ Steam (650 psi): 120kpph
- ▶ Steam (125 psi): 38.5kpph
- ▶ Hot Water: 187MMBTUH
- ▶ Chilled Water: 26,200 tons



# Functionality

- ▶ Black Start
  - Restore campus loads during Utility outage
- ▶ Emergency Generation
  - Pick up critical loads in 10s
- ▶ Microgrid
  - Island Mode/Gold Days
- ▶ Load Shed/Power Management System
  - Automatically sheds non-critical loads
  - Maintains spinning reserve
- ▶ Thermal Energy Storage
  - Peak load shedding and black start capacity
- ▶ Dual-Fuel Capability
  - Can run on FO for 72hrs allowing interruptible NG agreement

# FDA White Oak ESPCII Retro-Cx

## Cx Challenges

- ▶ Multiple stakeholders/interested parties
  - 3<sup>rd</sup> party Cx oversight by GSA (Owner) consultant
  - Tenant (FDA) input/coordination
- ▶ Existing Plant
  - Contractors no longer on site
  - Operations group in control of systems

## Solutions

- ▶ Honeywell brought in 3<sup>rd</sup> party (BMcD) to satisfy Owner
- ▶ Thorough pre-testing/issues resolution
- ▶ 3<sup>rd</sup> Party Cx consultant and tenant buy-in/engagement at each step
- ▶ Leverage available engineering and O&M staff for pre-testing and issues resolution prior to engaging contractors

# FDA White Oak ESPCIII Cx

## Cx Challenges

- ▶ Phased Implementation
  - Four separate contractual milestones:
    - ▶ Hot Water
    - ▶ Cooling
    - ▶ Steam
- ▶ ~~Complex~~ Power Integration
  - Three steam pressure levels
  - CHW temperature reset coordination with TES
  - NG crossover and fuel swap
- ▶ Critical Active Loads
  - Campus labs/vivariums can't lose utilities
  - STG trip testing steam disturbance
  - Blackstart requires we "pull the plug"

## Solutions

- ▶ Full Time Field Oversight
  - Cx Lead on-site 15mo+
  - Subject matter experts on-site as required
- ▶ Thoughtful grouping of systems
- ▶ In-depth controls review/verification
  - SDS Review
  - Witness of SFAT
  - In-field verification of ladder logic
- ▶ Detailed Verification/Creative Approach
  - Thorough vetting at each phase
  - TES for simulated site loads
  - Simulation software for LMS/PMS
  - EGEN farm and Aux boiler for quick restoration

# Q&A

Nick Rauth  
Burns & McDonnell  
*OnSite* Energy & Power  
919-900-1888  
[nrauth@burnsmcd.com](mailto:nrauth@burnsmcd.com)

