



Public Services and Procurement Canada Services publics et Approvisionnement Canada

Cliff Street Temporary Boiler Plant

RPB

Presentation to – International District Energy Association (IDEA) Conference St. Paul, Minnesota June 2016 by Tomasz Smetny-Sowa Director, Energy Services Acquisition Project





Making the Impossible a Reality

Under extraordinary circumstances, people are sometimes called upon to perform seemingly impossible tasks

Building the Cliff Temporary Boiler Plant (TBP) was such a task!






The Cliff

- Original plant:
 - nominal 190 MW (650,000 PPH) heating capacity
 - 100 MW (28,000 tons) cooling
 - Canada's largest central heating and cooling plant
- Supply steam and chilled water through 15 kilometres of tunnels
- Serves 52 office buildings downtown Ottawa, including Parliament buildings
- On October 19, 2009, boiler #1 exploded
- Complete loss of steam production



Cliff Plant





Think Fast

- The day after the explosion, on October 20, 2009, a decision to increase immediately the capacity at an interconnected plant at the National Printing Bureau (NPB), located across the river in Gatineau, Quebec
- On October 23, 2009, a decision to construct the new heating plant on the parking lot behind the original Cliff Plant and next to the Supreme Court of Canada
- On November 2, 2009, Construction of the Temporary Boiler Plant (TBP) starts



After the explosion





Phase I – Provide Heating

Day 1: Monday, November 2, 2009 The Supreme Court parking lot becomes a construction site



調査に通




A lot to deal with!

While constructing the new Cliff TBP the project team dealt with many simultaneous, independent but related initiatives:

- Ensuring available steam capacity was shared appropriately between buildings;
- Tracking the weather forecasts and adjusting deadlines accordingly to meet the demand;
- Assisting the incident investigators to understand the Cliff operations and procedures;
- Abating of all accessible asbestos in the original Cliff Plant (boiler room and chiller room).



Cliff steam demand forecast October – December 2009







Multiple challenges

- Three concurrent methods of production capacity increase at the same time
 - NPB installation of additional inside boilers
 - NPB installation of portable outside boilers
 - Cliff TBP construction
- Planning ahead for the superheated steam production:
 - Ensure that the additional boilers were in place for the cooling season (Phase II of the construction project)
 - Incorporate long-term plans to rehabilitate the entire Cliff Plant in the most economical way





Changes by the hour



Day 6: Four Saturated Steam Boilers arrive on site

Day 7: Installation of saturated steam boilers on the concrete slab while constructing the remaining portion of the plant





All boilers in place




Day 9: Foundation constructions in progress





Time: The Driver of all decisions

- Most decisions based on:
 - The availability of the material
 - The speed at which it could be delivered
 - The fastest method of installation







And the work goes on and on...

- Day 12: Feed water pumps arrive and piping installation starts
- Day 17: Connection to existing steam and condensate distribution within plant staircase
















Work Continues

- Day 19: Main steam header installation
- Day 22: Electrical cable and piping installation linking the new plant and the old





Day 22







Building it from the inside out




"Inside-out" because the project schedule needed to be inverted: the boilers would be installed first and the building would be built around them





From ground to steam in 37 days

- No roof or walls but we had steam!
- On December 8, 2009, just 37 days after the shovel broke the ground, Boilers #1 and #2 started to produce steam. Six days later, steam was feeding the main network.









Work continues in rain or shine (or sleet)...



Day 38





Phase II – Cooling

- Now that the heating capacity was restored, the team had to resolve the cooling capacity issue
- The chillers in the Cliff Chiller Plant, although still functional after the explosion, were driven by turbines that required superheated steamproducing boilers to operate
- Additional superheated steam boilers had to be installed prior to the cooling season; Phase II began



Restoration and construction continues





Phase II Progress

- On February 22, 2010, the floor slab of the Plant addition was completed
- By March 13, 2010, three Superheated Steam Boilers were installed
- On March 26, 2010, the steel frame of the addition was completed




Installation of the steam boilers





Phase II – The Challenges

- Multiple trades were constructing different building systems simultaneously, resulting in a jungle of scaffolding
- Adding to the project schedule the design and construction of a new condensate return system as the original one couldn't be used, it was in the asbestos contaminated building








The necessity of conducting a steam blow - a dangerous and loud process - in downtown Ottawa! The design, manufacture and delivery of a special muffler that allowed the success of the steam blow process was one of the great successes of Phase II







Final Steps



New Plant, landscaping completed

- The chilled water production started on May 4, 2010
- By mid-May, the entire project was substantially completed





Completion



June 6 – final inspection

June 15 – the official completion date of the TBP

Final inspection






Energy Service Acquisition Project - ESAP

- The ESAP program is a Public Services and Procurement Canada (PSPC) initiative to modernize PSPC heating and cooling infrastructure within the National Capital Region (NCR)
- Within the NCR, PSPC owns and operates the six Central Heating and Cooling Plants (CHCP) that provide heating and/or cooling for more than 80 buildings in the NCR through five district heating and cooling systems



Canada

ESAP CHCP locations







Energy Service Acquisition Project - ESAP

- The ESAP program, initiated in 2009, is responsible for determining the best way to upgrade the District Energy Systems (DES) and to arrange for a transformation of the responsibility for the upgrade or modernization and ongoing operation
- With the launch of the ESAP in 2009, PSPC decided to take a holistic approach to its energy services infrastructure
- In response to this mandate, PSPC developed a proposal to fundamentally redefine and improve the delivery of heating and cooling services in the NCR





Energy Service Acquisition Project - ESAP

ESAP aims to:

- Reduce Greenhouse Gas Emissions to improve the Government of Canada's environmental performance
- Reduce the costs of heating and cooling services for the federal Government
- Increase the safety and reliability of heating and cooling operations
- Leverage the private sector's innovation, capacity, and expertise





Next Steps

- Fall 2016, Treasury Board Submission
- Spring 2017, Request For Qualification issued
- Fall 2017, Request for Proposal issued
- Summer 2019, contract signed
- Spring 2020, 5-year conversion period starts
- Spring 2055, contract ends



Canada

Questions?



