



Decommissioning of a Processing Plant and CHP Systems

Presented by **CHA Consulting, Inc.**

Hailey Slamka, MEng, EIT
Electrical Engineer (High Voltage Electrical Group)

Chris Csernyei, M.E.Sc, P.Eng
Mechanical Engineer (Thermal Mechanical Group)



110TH ANNUAL CONFERENCE & TRADE SHOW | June 24-27
David L. Lawrence Convention Center and The Westin Convention Center | Pittsburgh, PA



Agenda



- Introduction
- Decommissioning Process
- Project Description
- Corrosion Inhibitors
- Electrical Decommissioning
- Mechanical Decommissioning
- Questions

Introduction

What?

Officially take a factory or other industrial building out of use and make the area safe.

Important considerations:

- Communicate
- Availability of information for existing equipment
- Existing procedures?
- Assist & recommend **DON'T** control & override



Decommissioning Process



Communication

CHP Plant Decommissioning PRESERVATION SIGN-OFF SHEET		HRSG						
SYSTEM:	HEAT RECOVERY STEAM GENERATOR (HRSG)							
DESCRIPTION:	HRSG - Fire Side, including Stack, Fans, Dampers and Ductwork							
P&ID	CB 627-02261 Sheet 4							
APPLICABLE INSTRUCTIONS:	NATCOM PI-1004							
PRESERVATION (Follow-up with inspection every 3-months)								
Initial Preservation:	<table border="1"> <thead> <tr> <th>GROUP</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		GROUP	DATE	CONTRACTOR:		LEAD:	
GROUP	DATE							
CONTRACTOR:								
LEAD:								
Volatile Corrosion Inhibitor = Contact Corrosion Inhibitor =								
Main Stack <input type="checkbox"/> Bypass Stack <input type="checkbox"/> Ductwork <input type="checkbox"/> Fresh Air Fan (625852) & Inlet <input type="checkbox"/> Augment Air Fan (625853) <input type="checkbox"/> Auxiliary Air Blower (625854) <input type="checkbox"/> Auxiliary Air Blower (625855) <input type="checkbox"/> Guillotine Damper <input type="checkbox"/> Bypass Stack Damper <input type="checkbox"/> TEG Air Damper <input type="checkbox"/> Fresh Air Damper <input type="checkbox"/> Augmenting Air Dampers <input type="checkbox"/> TEG Exhaust Duct <input type="checkbox"/>								
Remarks:								
3-month inspection:	<table border="1"> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		CONTRACTOR:		LEAD:			
CONTRACTOR:								
LEAD:								
6-month inspection:	<table border="1"> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		CONTRACTOR:		LEAD:			
CONTRACTOR:								
LEAD:								
9-month inspection:	<table border="1"> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		CONTRACTOR:		LEAD:			
CONTRACTOR:								
LEAD:								
12-month inspection:	<table border="1"> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		CONTRACTOR:		LEAD:			
CONTRACTOR:								
LEAD:								
15-month inspection:	<table border="1"> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		CONTRACTOR:		LEAD:			
CONTRACTOR:								
LEAD:								
18-month inspection:	<table border="1"> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		CONTRACTOR:		LEAD:			
CONTRACTOR:								
LEAD:								
21-month inspection:	<table border="1"> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		CONTRACTOR:		LEAD:			
CONTRACTOR:								
LEAD:								
24-month inspection:	<table border="1"> <tbody> <tr> <td>CONTRACTOR:</td> <td></td> </tr> <tr> <td>LEAD:</td> <td></td> </tr> </tbody> </table>		CONTRACTOR:		LEAD:			
CONTRACTOR:								
LEAD:								

End Goal

- Full or partial decommissioning?
- End result of equipment:
 - Demolition
 - Abandon in place
 - Preserve for future use
 - Preserve for sale (i.e. relocation)

Deliverable

- How will the end goal be communicated?
- Possible deliverables:
 - Decommissioning procedures
 - Preservation instructions
 - Checklists
 - Report
 - Photographs

Project Description



Facility: Processing plant equipped with Solar Taurus 70 GTG package w/ HRSG, and Solar Centaur 40 GTG package w/ HRSG


End Goal

- Part of the plant was to remain with limited function
- Remainder of plant to be decommissioned
 - Equipment with motors >100HP to be preserved
 - GTG's to be relocated
 - Remaining equipment will be abandoned in place or returned to vendors

Deliverable

- No established deliverable (worked with the client to determine appropriate deliverable)

Corrosion Inhibitors



Different Application Types

- Oil additive
- Aerosol
- Pouch
- Coating
- Emitter
- Device
- Grease

Electrical Decommissioning

Electrical Decommissioning




Availability of Information

- Existing single line was out of date
- No documentation of existing MCC configurations and loads

Steps Taken

- Survey entire facility
- Updated existing SLD for reference
- Record every MCC and MCC load within each E-Room within the facility
- Generate a table for each E-Room listing all MCCs/loads





Generation of Deliverables



- Create a preliminary decommissioning checklist
 - Determined which loads were to be shut down/remain active
- Submitted for client to review and adjust
- Create a set of decommissioning instructions for contractor
- Finalize checklist with following details:
 - End State
 - Layup/preservation requirements
 - Decommission Date
 - Electrical Contractor sign off
- Create a list of instructions/procedures and final report

Decommissioning Instructions



- **MCC Load Decommissioning Procedure**
 - Lockout/Tagout at each MCC bucket/local disconnects (if applicable)
 - Inject preservatives into decommissioning MCC buckets
 - For fully decommissioned MCCs, lockout/tagout at upstream substation
- **HV Switchyard Decommissioning Procedure**
 - Remain as is per utility agreement (will vary, based on project)
- **HV Switchgear/CHP Decommissioning Procedure**
 - Same as MCC Load Decommission with the addition of:
 - E.O.D.O breakers – racked out with control fuses removed, lockout/tagout
 - Relay Software – download and give copies to client
 - Annual switchgear cleaning

	Plant Decommissioning Electrical Instructions	E-Rooms and MCCs
--	--	-----------------------------

NOTE: This is a general list of instructions for how the electrical equipment decommissioning is to be conducted.

List of Instructions:

Decommissioning of MCCs:

- Follow the electrical decommissioning checklist, categorized by electrical room and MCC to determine which loads are to be kept active and which loads are to be decommissioned.

NOTE: All spare breakers and breakers with blank labels are to be decommissioned.

- For loads being decommissioned, follow electrical LOCKOUT / TAGOUT procedure and process LOCKOUT / TAGOUT procedure. Keys to be handed over to the plant manager.
- Ensure any motor load with local disconnects undergo LOCKOUT / TAGOUT procedure at the local disconnect in addition to its corresponding MCC breaker. Keys to be handed over to the plant manager.
- All the decommissioned switchgears, panels, MCCs, and junction boxes to be preserved against corrosion.

Preservation and Inspection of MCC Motor Loads:

- For motors of 100HP or greater being preserved, refer to the corresponding MESI for instruction details.

Decommissioning of Substations and Switchyards:

- Substation configurations are to be left "as is" unless otherwise noted.
- Decommissioning of MCCs must be completed prior to making configuration alterations to the substations and switchyards.
- Substation 1 and 2:
 - Substation 1 will be used to provide power to the downstream switchgear.
 - Substation 2 will be decommissioned.
 - Follow electrical LOCKOUT/TAGOUT procedure for substation 2 fused switch found in the HV switchgear located in the switchyard. Keys to be handed over to the plant manager.
- Substation 4:
 - Substation 4 will be decommissioned.
 - Follow electrical LOCKOUT/TAGOUT procedure for the following switchgear circuit breakers located within ER-10: substation 4 low voltage main breaker, MCC 4-1, MCC 4-2, MCC 4-3, MCC Y-D, cap banks, and spare. Keys to be handed over to the plant manager.
 - Follow electrical LOCKOUT/TAGOUT procedure for primary substation 4 transformer fused switch found in the HV switchgear located in the switchyard. Keys to be handed over to the plant manager.
- Substation 5:

REV 01


Page 1 of 2

Plant Decommissioning ELECTRICAL E-ROOM AND MCC CHECKLIST (E-Room 2)											Date:	02/11/2019
											CHA Project No:	
											Rev:	PA
Dwg Ref.	Tag No.	Equipment / Material	Decommissioning Date	Decommissioning By	End State	Location / Boundary	Recommendations	Layout Requirement	Preservation Measures	Remarks	Inspection Date	
											Contractor	CHA
	525212	ISO Column Sump Pump		N/A	Closed	5C		N/A		Break Station		1/28/2019
		Welding Receptacle EI. 100ft. Col E.7		Contractor	Lock and Tag	5D		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
		Welding Receptacle EI. 100ft. Col B.6		Contractor	Lock and Tag	5D		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
		Size 1 Spare w/CPT		Contractor	Lock and Tag	5E		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
		No Tag		Contractor	Lock and Tag	5F		Switch off the disconnect. Lock and tag.				1/28/2019
		Welding Receptacle EI. 124ft. Col D.7		N/A	Closed	5F		N/A				1/28/2019
		Space		N/A		6A		N/A				1/28/2019
		Space		N/A		6B		N/A				1/28/2019
		Space		N/A		6C		N/A				1/28/2019
	725201	Adsep Recir Pump #1		Contractor	Lock and Tag	6D		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-105 Emitter			1/28/2019
	23811	Fiber Pre-Dewtr. Paddle Screen #3		Contractor	Lock and Tag	7A		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-105 Emitter			1/28/2019
	72520	Adsep Recir Pump #2		Contractor	Lock and Tag	7B		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-105 Emitter			1/28/2019
Equipment MCC 2-1 (Rear)												
	716703	Bulk Carbon Rotary Airlock		Contractor	Lock and Tag	1A		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	716704	Filter Aid Conveyor		Contractor	Lock and Tag	1B		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	718891A	CarbonHopper Dust Collector Index Drive		Contractor	Lock and Tag	1C		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
		Space		N/A		1D		N/A				1/28/2019
	718893A	Flt. Aid Hopper Dust Collector Bag Cleaner		Contractor	Lock and Tag	1E		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	718893B	Flt. Aid Hopper Dust Collector Index Drive		Contractor	Lock and Tag	1F		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	735221	Adsep De-rator Sup Pmp		Contractor	Lock and Tag	2A		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	458103	Precoat Tank Agitator		Contractor	Lock and Tag	2B		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	455206	Precoat Tank Pump		Contractor	Lock and Tag	2C		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-111 Pouch			1/28/2019
		Space		N/A		2D		N/A				1/28/2019
	716702	Flt. Aid Hopper Rotary Airlock		Contractor	Lock and Tag	2E		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	435206	Seal Water Return Pump		Contractor	Open	3A		Switch off the disconnect. Lock and tag.		Future Decommissioning		1/28/2019
	436701	Spent Filter Aid Conveyor		Contractor	Lock and Tag	3B		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	438101	Filter Aid Slurry Agitator		Contractor	Lock and Tag	3C		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
	715896	Filter Aid Hopper Exhaust Fan		Contractor	Lock and Tag	3D		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019
		Blank Label		Contractor	Lock and Tag	3E		Switch off the disconnect. Lock and tag.				1/28/2019
	715897	Carbon Hopper Dust Fan		Contractor	Lock and Tag	3F		Switch off the disconnect. Lock and tag.	Cortec VpC-239 Aerosol, Cortec VpCI-101 Device			1/28/2019

Mechanical Decommissioning

Mechanical Decommissioning

STKDC#		Party Responsible: Operations	
Unit Name: Grind Tanks		Time Est.:	
Material:		Cost Est.:	
PRESERVATION REQUIRED?: YES			
Material Required:			
Permits Required:		Multiple Energy Source Inventory	
MESI HOT WORK CONF		Equipment Number S155202	
Equipment / Equipment number		Location: Wet End Inside, 1st Floor, Off 2nd Grind tank	
1 1st Grind Overflow Tank		P & ID: 215-D2003 Inventory conducted by: Date: BOP history:	
2 1st Grind Tank		STEP 1: ELECTRICAL LOCKOUT / TAGOUT	
3 2nd Grind Tank		Equipment Number S155202 First Lock On Installed by: Last Lock Off Removed By:	
4 Germ Filtrate Tank		E-Room Location ER4-1-3 FSC Lock Number:	
5 Drains Tank		Description Pump	
1 1st Grind Overflow Tank Agitator		STEP 2: PROCESS LOCKOUT / BLOCKOUT Attention: It may be necessary to disconnect air lines for plunger and auto valves.	
2 1st Grind Pump		Equipment Description / Location	
3 2nd Grind Pump		Close manual PLUNGER valve at tank discharge Installed By: Removed By:	
4 Grind Sump Pump		Equipment Description / Location	
5 1st Grind Overflow Vent Fan		Close Auto Valve on discharge from pump Installed By: Removed By:	
		Equipment Description / Location	
		Close manual valve for flush supply at pump Installed By: Removed By:	
		STEP 3: ISOLATION VERIFICATION	
		Equipment Description / Location	
		Open drain line on supply side of pump	
		*Please note that if product continues to drain from this line additional blocking/blinding may be necessary.	



- What?
 - GTG
 - HRSG/WHB
 - Deaerator
 - Gas Compressor(s)
 - Chemical systems
 - Pumps & Blowers
 - Piping
 - Process equipment
- Where is it located?
- How will it be decommissioned?
- Same 3 steps for **ALL** equipment:
 - Disconnected (LOTO) > Clean > Seal

GTG



- T70 & C40
- Preserved by equipment vendor (Solar)
- Borescope inspection and equipment assessment (Solar)
- GT skid & generator (preserved)
- Lube oil system (leave in service)
- Controls (preserved)


HRSG




- Gas side & water side
- Purge gas path
- General inspection of drums
- Drain > clean > seal
- Vapor corrosion inhibitor for internals
- Contact corrosion inhibitor for externals
- Wrap exposed areas where water ingress could occur (i.e. PSV trough region)



- Chemical feed:
 - tubing drained & purged (nitrogen then compressed air) then returned to vendor
 - Chemical vendor instructions to be followed
- Deaerator
 - Drained and inspected
 - Vapor corrosion inhibitor for internals
 - Open ends sealed
 - NPFA 57 for safe venting
- Gas Compressor
 - NPFA 57 for safe venting
 - Fuel gas piping to be purged with nitrogen; 5 – 10 psig nitrogen fill for layup
 - Gas compressor skids to be purged and prepared for return to vendor



- Pumps & Blowers:
 - Identify access point (fittings/flanges/valves)
 - Clean
 - Internal (vapor) & external (contact) corrosion inhibitors
 - Bearings (grease inhibitor/oil inhibitor)
 - Wrap exposed shafts
- Piping
 - Ammonia – nitrogen then air purge; clean & dry; internal & external inhibitors; seal
 - Fuel gas – nitrogen purge; 5-10 psig nitrogen layup
 - Instrument air - nitrogen purge; 5-10 psig nitrogen layup
 - Feedwater – drain; clean & dry; internal & external inhibitors; seal
 - “As-is” – Drain; dry; seal



THE FOLLOWING IS A GENERAL OVERVIEW OF THE PUMP DECOMMISSIONING PROCESS. REFER TO COMPLETE PUMP DECOMMISSIONING/PRESERVATION PROCEDURE INSTRUCTIONS IN MESI BOOK.

TYP. (2):


1. CLOSE PUMP SUCTION AND DISCHARGE VALVES.
2. REMOVE EXPANSION JOINT.
3. INSERT VAPOR CORROSION INHIBITOR.
4. INSTALL BLANK ON PUMP OPENINGS.




Process equipment (to be preserved)

TYP. (2) PER FIBER MILL
1. BREAK FLANGES TO ISOLATE FIBER MILL FROM PROCESS PIPING.
2. INSERT VAPOR CORROSION INHIBITOR.
3. INSTALL BLANK ON PIPE OPENINGS.

THE FOLLOWING IS A GENERAL OVERVIEW OF THE FIBER MILL DECOMMISSIONING PROCESS. REFER TO COMPLETE FIBER MILL DECOMMISSIONING/PRESERVATION PROCEDURE INSTRUCTIONS IN MESI BOOK.



- Empty & clean
- Apply internal & external corrosion inhibitors
- Seal openings



Major deliverables

- Contractor scope of work
- Preservation instructions
- Preservation check-lists
- Photographs
- Index of mechanical equipment

CHP Plant Decommissioning Equipment Preservation Instructions		HRSG/WHB
<p>WARNING Ensure all safety procedures are understood and adhered to, and proper LOCKOUT/TAGOUT procedures have been conducted prior to conducting the preservation process of equipment.</p> <p>NOTES: 1. This is a general list of instructions for how preservation is to be conducted. Refer to Ingreion's specific requirements/directions, if applicable, for each item that is to be preserved. 2. Follow instructions from corrosion inhibitor vendor relating to product specific application concentration / spread rate / film thickness; and the associated application methods. 3. Refer to picture of the equipment for equipment isolation and blanking requirements.</p> <p>Initial Preservation List of Instructions:</p> <p><u>General:</u></p> <ol style="list-style-type: none"> 1. Electrical LOCKOUT/TAGOUT procedure has been completed. 2. Equipment and Process LOCKOUT/TAGOUT procedure has been completed per Ingreion and Cleaver Brooks/NATCOM's operating instructions, including gas turbine generator, feedwater, chemical feed, steam, fuel gas, chemical feed, water, instrument air, and SCR ammonia system. 3. Follow equipment vendor's operating instructions for long term layup of equipment/devices as applicable. 4. Equipment has been vented and de-pressurized as applicable. 5. Observe Ingreion and chemical supplier's health and safety instructions/requirements for handling aqueous ammonia. Personal protective equipment is required. 6. Follow Ingreion's Confined Space Hazard policy for confined space entry. 7. For stainless steel equipment and piping, ensure equipment and piping is generally clean, dry and properly sealed. Preservation by corrosion inhibitor is not required. <p><u>Water Side:</u></p> <ol style="list-style-type: none"> 1. Water side applies to boiler proper, economizer, feedwater piping, steam piping, and all interconnecting auxiliary piping. 2. Carry out general inspection of equipment and record conditions that require attention. 3. Inspect drum internal and record conditions. 4. Drain equipment thoroughly. 5. Boiler drums should have been cleaned by blowdown before unit shutdown. Clean up debris from steam drum(s) and lower drum(s) as applicable. 6. Break flanges for inlet and outlet process pipes of HRSG/WHB piping as indicated. 7. HRSG/WHB must be dry before corrosion inhibitor is applied. 8. Apply vapor corrosion inhibitor to HRSG/WHB internals including piping internals. 9. Apply contact solid film type corrosion inhibitor to outdoor process valves and devices. 		



CHP Plant Decommissioning PRESERVATION SIGN-OFF SHEET		HRSG																										
<p>SYSTEM: HEAT RECOVERY STEAM GENERATOR (HRSG)</p> <p>DESCRIPTION: HRSG - Fire Side, including Stack, Fans, Dampers and Dustwork</p> <p>P&ID: CB 627-02261 Sheet 4</p> <p>APPLICABLE: NATCOM PI-1004</p> <p>INSTRUCTIONS: HRSG/WHB</p>																												
<p>PRESERVATION (Follow-up with inspection every 3-months)</p>		<p>SIGN-OFFS</p>																										
<p>Initial Preservation: Volatile Corrosion Inhibitor = Contact Corrosion Inhibitor =</p>		<p>CONTRACTOR: _____</p> <p>LEAD: _____</p>																										
<p>Completed:</p> <table border="0"> <tr><td>Main Stack</td><td><input type="checkbox"/></td></tr> <tr><td>Bypass Stack</td><td><input type="checkbox"/></td></tr> <tr><td>Ductwork</td><td><input type="checkbox"/></td></tr> <tr><td>Fresh Air Fan (625852) & inlet</td><td><input type="checkbox"/></td></tr> <tr><td>Augment Air Fan (625853)</td><td><input type="checkbox"/></td></tr> <tr><td>Auxiliary Air Blower (625854)</td><td><input type="checkbox"/></td></tr> <tr><td>Auxiliary Air Blower (625855)</td><td><input type="checkbox"/></td></tr> <tr><td>Guillotine Damper</td><td><input type="checkbox"/></td></tr> <tr><td>Bypass Stack Damper</td><td><input type="checkbox"/></td></tr> <tr><td>TEG Air Damper</td><td><input type="checkbox"/></td></tr> <tr><td>Fresh Air Damper</td><td><input type="checkbox"/></td></tr> <tr><td>Augmenting Air Dampers</td><td><input type="checkbox"/></td></tr> <tr><td>TEG Exhaust Duct</td><td><input type="checkbox"/></td></tr> </table>		Main Stack	<input type="checkbox"/>	Bypass Stack	<input type="checkbox"/>	Ductwork	<input type="checkbox"/>	Fresh Air Fan (625852) & inlet	<input type="checkbox"/>	Augment Air Fan (625853)	<input type="checkbox"/>	Auxiliary Air Blower (625854)	<input type="checkbox"/>	Auxiliary Air Blower (625855)	<input type="checkbox"/>	Guillotine Damper	<input type="checkbox"/>	Bypass Stack Damper	<input type="checkbox"/>	TEG Air Damper	<input type="checkbox"/>	Fresh Air Damper	<input type="checkbox"/>	Augmenting Air Dampers	<input type="checkbox"/>	TEG Exhaust Duct	<input type="checkbox"/>	<p>CONTRACTOR: _____</p> <p>LEAD: _____</p>
Main Stack	<input type="checkbox"/>																											
Bypass Stack	<input type="checkbox"/>																											
Ductwork	<input type="checkbox"/>																											
Fresh Air Fan (625852) & inlet	<input type="checkbox"/>																											
Augment Air Fan (625853)	<input type="checkbox"/>																											
Auxiliary Air Blower (625854)	<input type="checkbox"/>																											
Auxiliary Air Blower (625855)	<input type="checkbox"/>																											
Guillotine Damper	<input type="checkbox"/>																											
Bypass Stack Damper	<input type="checkbox"/>																											
TEG Air Damper	<input type="checkbox"/>																											
Fresh Air Damper	<input type="checkbox"/>																											
Augmenting Air Dampers	<input type="checkbox"/>																											
TEG Exhaust Duct	<input type="checkbox"/>																											
Remarks:																												
3-month inspection:		CONTRACTOR: _____ LEAD: _____																										
6-month inspection:		CONTRACTOR: _____ LEAD: _____																										
9-month inspection:		CONTRACTOR: _____ LEAD: _____																										
12-month inspection:		CONTRACTOR: _____ LEAD: _____																										
15-month inspection:		CONTRACTOR: _____ LEAD: _____																										
18-month inspection:		CONTRACTOR: _____ LEAD: _____																										
21-month inspection:		CONTRACTOR: _____ LEAD: _____																										
24-month inspection:		CONTRACTOR: _____ LEAD: _____																										

MECHANICAL EQUIPMENT DECOMMISSIONING SCOPE															CHS Rev: 09/02/2016 PA	
Draw Ref.	Tag No.	Equipment / Material	Decommissioning Date	Decommissioning By	End State	Location / Boundary	Material / Design Condition	Condition before Shutdown / Medium in Pipe System	Inspection / Testing before Decommissioning	Action prior to Layup	Provisions req'd for Layup	Layup Requirement	Action req'd during Layup Period	Reference Photographs	Remarks	Rev
Gas Turbine Generator System (TGS)																
		OT Seal and Generator	Nov 15, 2018 To be confirmed	Solar	Preservation mode except tube oil system	From OT air inlet to exhaust		Operating equipment	N/A	* All openings to be sealed	by Solar	by Solar	by Solar		* Borescope inspection of valves before removal the unit	
		Lube Oil System	Nov 15, 2018 To be confirmed	Part of Solar's scope	Leave in Service			Lube oil	As required by Solar	* Corrosion inhibitor added to lube oil per Solar instructions	by Solar	by Solar	by Solar		* Lube oil system is required for periodic turning of turbine and generator	
		Generator and OTG Controls	Nov 15, 2018 To be confirmed	Part of Solar's scope	Preserved as part of Electrical Equipment				by Solar	by Solar	by Solar	by Solar	by Solar			
Heat Recovery Steam Generator																
		Steam Side (includes economizer)	When OTG shutdown	Contractor	Decommission	From feedwater control	OTG area	Steam (H ₂ O) gas operation	General inspection	* Unattended blowdown lines	N/A	* No external manipulation	* General inspection (over 3			

Heat Recovery Steam Generator																
		HRSG - Water Side, including economizer, feedwater piping and steam piping	when OTG mobilized	Contractor	Preservation mode	From feedwater valve to steam stop										
		HRSG - Fire Side, including bypass stack, ductwork	when OTG mobilized	Contractor	Preservation mode	From bypass main										
		Chimneys - Gullotine Chimney, Bypass Stack Chimney, TEO Air Chimney, Fresh Air Chimney, Augmenting Air Chimneys	when OTG mobilized	Contractor	Preserved as part of HRSG fire side	Part of fire side										
		Pre-Heat Air Fan, Augmenting Air Fans, and Auxiliary Air Blowers	when OTG mobilized	Contractor	Preservation mode	Equip										
		Dust Burner and Fuel Train Skid, including burner	when OTG mobilized	Contractor	Preserved as part of HRSG fuel gas piping											
		OMS and HRSG Control Panel	when OTG mobilized	Contractor	Preserved as part of Electrical Panels											
		Steam Drum Piping	when OTG mobilized	Contractor	Preserved as part of HRSG Water Side	Equip										
		Core Blowdown Heat Recovery & Piping Blowdown Tank & Piping	when OTG mobilized	Contractor	Preservation mode	Equip										
WATCOMP-1003																
		SCR Antenna Skid	when OTG mobilized	Contractor	Preservation mode	From hot media case valve										

EQUIPMENT PRESERVATION SUMMARY LIST (Equipment with motor 100 HP and larger)										Date:	11/14/2018
										CHA Project No.:	35099
										Rev:	PA
Book/MESI	Item	Description	Tag	HP	System	Category	Preserve Motor	Preserve Equipment	Comment		
1	3	Corn Unloading Dust Collector Fan	115892	100	Corn Unloading	Blower/Fan	Y	Y			
	9	E-1 Bucket Elevator	116703	125	Corn Unloading	Elevator/Conveyor/Misc fans&pumps	Y	Y			
	10	E-2 Bucket Elevator	116704	200	Corn Unloading	Elevator/Conveyor/Misc fans&pumps	Y	Y			
	14	O-7 Corn Supply Conveyor	116719	100	Corn Unloading	Elevator/Conveyor/Misc fans&pumps	Y	Y			
3	1	Steep Advance Pump (Recirculation)	145201	125	Corn Steeping		Y	Y			
	2	West Sluice Pump	145202	125	Corn Steeping						
	17	East Sluice Pump	145231	125	Corn Steeping						
4	2	1st Grind Pump	155201	150	Corn Grinding						
	3	2nd Grind Pump	155202	125	Corn Grinding						
	11	1st Grind Mill #1	158901	100	Corn Grinding						
	12	1st Grind Mill #2	158902	100	Corn Grinding						
	14	2nd Grind Mill #1	158903	100	Middlings Concentration						
7	15	2nd Grind Mill #2	158904	150	Middlings Concentration						
	1	Fiber Sep Supply Pump	165201	125	Fiber Separation						
	2	1st Fiber Wash Supply Pump	165202	125	Fiber Separation						
	3	2nd Fiber Wash Supply Pump	165204	125	Fiber Separation						
	28	Fiber Mill #1	168901	600	Fiber Separation						
9	29	Fiber Mill #2	168902	600	Fiber Separation						
	1	Primary Supply Pump	175201	100	Primary Separation						
	11	Middling Concentrator	178802	200	Primary Separation						
	12	Primary Separator - Small	178803	150	Primary Separation						
	14	Primary Separator - Big	178812	300	Primary Separation						
10	22	IMST - Mill Starch Thickener	188801	150	Middlings Concentration						
	4	2nd Stage Pump	195205	100	Starch Washing						
	5	3rd Stage Pump	195206	100	Starch Washing						
	6	4th Stage Pump	195207	100	Starch Washing						
	7	5th Stage Pump	195208	100	Starch Washing						
	8	6th Stage Pump	195209	100	Starch Washing						
	9	7th Stage Pump	195210	100	Starch Washing						
	10	8th Stage Pump	195211	100	Starch Washing						
	11	9th Stage Pump	195212	100	Starch Washing						
	12	10th Stage Pump	195213	100	Starch Washing						
11	13	11th Stage Pump	195214	100	Starch Washing						
	14	12th Stage Pump	195215	100	Starch Washing						
	15	13th Stage Pump	195216	100	Starch Washing						
	18	ABS to Starch Station	195219	100	Starch Washing						
	19	ABS to Starch Station	195220	100	Starch Washing						
	11	Starch Dryer Fan West (#1)	315891	200	Starch Dewatering/Drying	Blow					
	12	Starch Dryer Fan East (#2)	315894	200	Starch Dewatering/Drying	Blow					
27	15	Starch Transport Blower	316702	100	Starch Dewatering/Drying	Elevator/Convey					
	27	Starch Dewatering Centrifuge (reineveld) Main Drive	318803	200	Starch Dewatering/Drying						



Conclusion



Thank You

For more information, please contact:

Hailey Slamka, MEng, EIT

Electrical Engineering
High Voltage Electrical Group
p. 289-273-7334
e. hslamka@chacompanies.com

Christopher Csernyei, P.Eng

Mechanical Engineer
Thermal Mechanical Group
p. 289-273-7098
e. ccsernyei@chacompanies.com



110TH ANNUAL CONFERENCE & TRADE SHOW | June 24-27
David L. Lawrence Convention Center and The Westin Convention Center | Pittsburgh, PA

